



HAL
open science

Characterizing and Mitigating Intraday Variability: Reconstructing Source Structure in Accreting Black Holes with mm-VLBI

Avery E. Broderick, Roman Gold, Boris Georgiev, Dominic W. Pesce, Paul Tiede, Chunchong Ni, Kotaro Moriyama, Kazunori Akiyama, Antxon Alberdi, Walter Alef, et al.

► **To cite this version:**

Avery E. Broderick, Roman Gold, Boris Georgiev, Dominic W. Pesce, Paul Tiede, et al.. Characterizing and Mitigating Intraday Variability: Reconstructing Source Structure in Accreting Black Holes with mm-VLBI. *The Astrophysical journal letters*, 2022, 930, 10.3847/2041-8213/ac6584. insu-03713306

HAL Id: insu-03713306

<https://insu.hal.science/insu-03713306>

Submitted on 4 Jul 2022

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.



Distributed under a Creative Commons Attribution 4.0 International License



Characterizing and Mitigating Intraday Variability: Reconstructing Source Structure in Accreting Black Holes with mm-VLBI

Avery E. Broderick^{1,2,3} , Roman Gold^{4,5} , Boris Georgiev^{2,3,1} , Dominic W. Pesce^{6,7} , Paul Tiede^{6,7} , Chunchong Ni^{2,3,1} , Kotaro Moriyama^{5,8,9} , Kazunori Akiyama^{8,10,7} , Antxon Alberdi¹¹ , Walter Alef¹² , Juan Carlos Algaba¹³ , Richard Anantua^{7,6,14} , Keiichi Asada¹⁵ , Rebecca Azulay^{16,17,12} , Uwe Bach¹² , Anne-Kathrin Baczko¹² , David Ball¹⁸ , Mislav Baloković¹⁹ , John Barrett⁸ , Michi Bauböck²⁰ , Bradford A. Benson^{21,22} , Dan Bintley^{23,24} , Lindy Blackburn^{7,6} , Raymond Blundell⁶ , Katherine L. Bouman²⁵ , Geoffrey C. Bower^{26,27} , Hope Boyce^{28,29} , Michael Bremer³⁰ , Christiaan D. Brinkerink³¹ , Roger Brissenden^{7,6} , Silke Britzen¹² , Dominique Broguiere³⁰ , Thomas Bronzwaer³¹ , Sandra Bustamante³² , Do-Young Byun^{33,34} , John E. Carlstrom^{35,22,36,37} , Chiara Ceccobello³⁸ , Andrew Chael^{39,40} , Chi-kwan Chan^{18,41,42} , Koushik Chatterjee^{7,6} , Shami Chatterjee⁴³ , Ming-Tang Chen²⁶ , Yongjun Chen (陈永军)^{44,45} , Xiaopeng Cheng³³ , Ilje Cho¹¹ , Pierre Christian⁴⁶ , Nicholas S. Conroy^{47,6} , John E. Conway⁵ , James M. Cordes⁴³ , Thomas M. Crawford^{22,35} , Geoffrey B. Crew⁸

, Alejandro Cruz-Ororio⁵ , Yuzhu Cui (崔玉竹)^{48,9,49} , Jordy Davelaar^{50,51,31} , Mariafelicia De Laurentis^{52,5,53} , Roger Deane^{54,55,56} , Jessica Dempsey^{23,24,57} , Gregory Desvignes^{12,58} , Jason Dexter⁵⁹ , Vedant Dhruv²⁰ , Sheperd S. Doeleman^{7,6} , Sean Dougal¹⁸ , Sergio A. Dzib^{30,12} , Ralph P. Eatough^{60,12} , Razieh Emami⁶ , Heino Falcke³¹ , Joseph Farah^{61,62} , Vincent L. Fish⁸ , Ed Fomalont⁶³ , H. Alyson Ford¹⁸ , Raquel Fraga-Encinas³¹ , William T. Freeman^{64,65} , Per Friberg^{23,24} , Christian M. Fromm^{66,5,12} , Antonio Fuentes¹¹ , Peter Galison^{7,67,68} , Charles F. Gammie^{20,47,69} , Roberto García³⁰ , Olivier Gentaz³⁰ , Ciriaco Goddi^{70,71} , Arturo I. Gómez-Ruiz^{72,73} , José L. Gómez¹¹ , Minfeng Gu (顾敏峰)^{44,74} , Mark Gurwell⁶ , Kazuhiro Hada^{9,49} , Daryl Haggard^{28,29} , Kari Haworth⁶ , Michael H. Hecht⁸ , Ronald Hesper⁷⁵ , Dirk Heumann¹⁸ , Luis C. Ho (何子山)^{76,77} , Paul Ho^{15,24} , Mareki Honma^{9,49,78} , Chih-Wei L. Huang (黄磊)¹⁵ , Lei Huang^{44,74} , David H. Hughes⁷² , Shiro Ikeda^{10,79,80,81} , C. M. Violette Impellizzeri^{82,63} , Makoto Inoue¹⁵ , Sara Issaoun^{6,40} , David J. James⁸³ , Buell T. Jannuzi¹⁸

, Michael Janssen¹² , Britton Jeter¹⁵ , Wu Jiang (江悟)⁴⁴ , Alejandra Jiménez-Rosales³¹ , Michael D. Johnson^{7,6} , Svetlana Jorstad^{84,85} , Abhishek V. Joshi²⁰ , Taehyun Jung^{33,34} , Mansour Karami^{1,2} , Ramesh Karuppusamy¹² , Tomohisa Kawashima⁸⁶ , Garrett K. Keating⁶ , Mark Kettenis⁸⁷ , Dong-Jin Kim¹² , Jae-Young Kim^{88,33,12} , Jongsoo Kim³³ , Junhan Kim^{18,25} , Motoki Kino^{10,89} , Jun Yi Koay¹⁵ , Prashant Kocherlakota⁵ , Yutaro Kofuji^{9,78} , Patrick M. Koch¹⁵ , Shoko Koyama^{90,15} , Carsten Kramer³⁰ , Michael Kramer¹² , Thomas P. Krichbaum¹² , Cheng-Yu Kuo^{91,15} , Noemi La Bella³¹ , Tod R. Lauer⁹² , Daeyoung Lee²⁰ , Sang-Sung Lee³³ , Po Kin Leung⁹³ , Aviad Levish²⁵ , Zhiyuan Li (李志远)^{94,95} , Rocco Lico^{11,96} , Greg Lindahl⁶ , Michael Lindqvist³⁸ , Mikhail Lisakov^{12,97} , Jun Liu (刘俊)¹² , Kuo Liu¹² , Elisabetta Liuzzo⁹⁸ , Wen-Ping Lo^{15,99} , Andrei P. Lobanov¹² , Laurent Loinard^{100,101} , Colin J. Lonsdale⁸ , Ru-Sen Lu (路如森)^{44,45,12} , Jirong Mao (毛基荣)^{102,103,104} , Nicola Marchili^{98,12} , Sera Markoff^{105,106} , Daniel P. Marrone¹⁸ , Alan P. Marscher⁸⁴

, Iván Martí-Vidal^{16,17} , Satoki Matsushita¹⁵ , Lynn D. Matthews⁸ , Karl M. Menten¹² , Daniel Michalik^{107,22} , Izumi Mizuno^{23,24} , Yosuke Mizuno^{48,108,5} , James M. Moran^{7,6} , Monika Moscibrodzka³¹ , Cornelia Müller^{12,31} , Alejandro Mus^{16,17} , Gibwa Musoke^{105,31} , Ioannis Myserlis¹⁰⁹ , Andrew Nadolski⁴⁷ , Hiroshi Nagai^{10,49} , Neil M. Nagar¹¹⁰ , Masanori Nakamura^{111,15} , Ramesh Narayan^{7,6} , Gopal Narayanan³² , Iniyar Natarajan^{54,112} , Antonios Nathanail^{5,113} , Santiago Navarro Fuentes¹⁰⁹ , Joey Neilsen¹¹⁴ , Roberto Neri³⁰ , Aristeidis Noutsos¹² , Michael A. Nowak¹¹⁵ , Junghwan Oh¹¹⁶ , Hiroki Okino^{9,78} , Héctor Olivares³¹ , Gisela N. Ortiz-León^{101,12} , Tomoaki Oyama⁹ , Daniel C. M. Palumbo^{7,6} , Georgios Filippou Paraschos¹² , Jongho Park^{15,117} , Harriet Parsons^{23,24} , Nimesh Patel⁶ , Ue-Li Pen^{15,1,118,119,120} , Vincent Piétu³⁰ , Richard Plambeck¹²¹ , Aleksandar PopStefanija³² , Oliver Porth^{105,5} , Felix M. Pötzl^{122,12} , Ben Prather²⁰ , Jorge A. Preciado-López¹ , Hung-Yi Pu^{123,124,15} , Venkatesh Ramakrishnan^{110,125,126} , Ramprasad Rao⁶ , Mark G. Rawlings^{127,23,24} , Alexander W. Raymond^{7,6} , Luciano Rezzolla^{5,128,129} , Angelo Ricarte^{6,7}

, Bart Ripperda^{130,51} , Freek Roelofs^{6,7,31} , Alan Rogers⁸ , Eduardo Ros¹² , Cristina Romero-Cañizales¹⁵ , Arash Roshanineshat¹⁸ , Helge Rottmann¹² , Alan L. Roy¹² , Ignacio Ruiz¹⁰⁹ , Chet Ruszczyk⁸ , Kazi L. J. Rygl⁹⁸ , Salvador Sánchez¹⁰⁹ , David Sánchez-Argüelles^{72,73} , Miguel Sánchez-Portal¹⁰⁹ , Mahito Sasada^{131,9,132} , Kaushik Satapathy¹⁸ , Tuomas Savolainen^{133,126,12} , F. Peter Schloerb³² , Jonathan Schonfeld⁶ , Karl-Friedrich Schuster³⁰ , Lijing Shao^{77,12} , Zhiqiang Shen (沈志强)^{44,45} , Des Small⁸⁷ , Bong Won Sohn^{23,24,33,34,134} , Jason SooHoo⁸ , Kamal Souccar³² , He Sun (孙赫)²⁵ , Fumie Tazaki⁹ , Alexandra J. Tetarenko^{135,40} , Remo P. J. Tilanus^{18,31,82,136} , Michael Titus⁸ , Pablo Torne^{109,12} , Efthalia Traianou^{11,12} , Tyler Trent¹⁸ , Sascha Trippe¹³⁷ , Matthew Turk⁴⁷ , Ilse van Bemmelen⁸⁷ , Huib Jan van Langevelde^{87,82,138} , Daniel R. van Rossum³¹ , Jesse Vos³¹ , Jan Wagner¹² , Derek Ward-Thompson¹³⁹ , John Wardle¹⁴⁰ , Jonathan Weintraub^{7,6} , Norbert Wex¹² , Robert Wharton¹² , Maciek Wielgus¹² , Kaj Wiik¹⁴¹ , Gunther Witzel¹² , Michael F. Wondrak^{31,142} , George N. Wong^{143,144}

, Qingwen Wu (吴庆文)¹⁴⁵ , Paul Yamaguchi⁶ , Doosoo Yoon¹⁰⁵ , André Young³¹ , Ken Young⁶ , Ziri Younsi^{146,5} , Feng Yuan (袁峰)^{44,74,147} , Ye-Fei Yuan (袁业飞)^{23,24,148} , J. Anton Zensus¹² , Guang-Yao Zhao¹¹ , Shuo Zhang¹⁴⁹ , and Shan-Shan Zhao (赵彬彬)⁴⁴

- ¹ Perimeter Institute for Theoretical Physics, 31 Caroline Street North, Waterloo, ON N2L 2Y5, Canada; abroderick@perimeterinstitute.ca
- ² Department of Physics and Astronomy, University of Waterloo, 200 University Avenue W, Waterloo, ON N2L 3G1, Canada
- ³ Waterloo Centre for Astrophysics, University of Waterloo, Waterloo, ON N2L 3G1, Canada
- ⁴ CP3-Origins, University of Southern Denmark, Campusvej 55, DK-5230 Odense M, Denmark
- ⁵ Institut für Theoretische Physik, Goethe-Universität Frankfurt, Max-von-Laue-Straße 1, D-60438 Frankfurt am Main, Germany
- ⁶ Center for Astrophysics | Harvard & Smithsonian, 60 Garden Street, Cambridge, MA 02138, USA
- ⁷ Black Hole Initiative at Harvard University, 20 Garden Street, Cambridge, MA 02138, USA
- ⁸ Massachusetts Institute of Technology Haystack Observatory, 99 Millstone Road, Westford, MA 01886, USA
- ⁹ Mizusawa VLBI Observatory, National Astronomical Observatory of Japan, 2-12 Hoshigaoka, Mizusawa, Oshu, Iwate 023-0861, Japan
- ¹⁰ National Astronomical Observatory of Japan, 2-21-1 Osawa, Mitaka, Tokyo 181-8588, Japan
- ¹¹ Instituto de Astrofísica de Andalucía-CSIC, Glorieta de la Astronomía s/n, E-18008 Granada, Spain
- ¹² Max-Planck-Institut für Radioastronomie, Auf dem Hügel 69, D-53121 Bonn, Germany
- ¹³ Department of Physics, Faculty of Science, Universiti Malaya, 50603 Kuala Lumpur, Malaysia
- ¹⁴ Department of Physics & Astronomy, The University of Texas at San Antonio, One UTSA Circle, San Antonio, TX 78249, USA
- ¹⁵ Institute of Astronomy and Astrophysics, Academia Sinica, 11F of Astronomy-Mathematics Building, AS/NTU No. 1, Sec. 4, Roosevelt Rd., Taipei 10617, Taiwan, R.O.C.
- ¹⁶ Departament d'Astronomia i Astrofísica, Universitat de València, C. Dr. Moliner 50, E-46100 Burjassot, València, Spain
- ¹⁷ Observatori Astronòmic, Universitat de València, C. Catedrático José Beltrán 2, E-46980 Paterna, València, Spain
- ¹⁸ Steward Observatory and Department of Astronomy, University of Arizona, 933 N. Cherry Ave., Tucson, AZ 85721, USA
- ¹⁹ Yale Center for Astronomy & Astrophysics, Yale University, 52 Hillhouse Avenue, New Haven, CT 06511, USA
- ²⁰ Department of Physics, University of Illinois, 1110 West Green Street, Urbana, IL 61801, USA
- ²¹ Fermi National Accelerator Laboratory, MS209, P.O. Box 500, Batavia, IL 60510, USA
- ²² Department of Astronomy and Astrophysics, University of Chicago, 5640 South Ellis Avenue, Chicago, IL 60637, USA
- ²³ East Asian Observatory, 660 N. A'ohoku Place, Hilo, HI 96720, USA
- ²⁴ James Clerk Maxwell Telescope (JCMT), 660 N. A'ohoku Place, Hilo, HI 96720, USA
- ²⁵ California Institute of Technology, 1200 East California Boulevard, Pasadena, CA 91125, USA
- ²⁶ Institute of Astronomy and Astrophysics, Academia Sinica, 645 N. A'ohoku Place, Hilo, HI 96720, USA
- ²⁷ Department of Physics and Astronomy, University of Hawaii at Manoa, 2505 Correa Road, Honolulu, HI 96822, USA
- ²⁸ Department of Physics, McGill University, 3600 rue University, Montréal, QC H3A 2T8, Canada
- ²⁹ McGill Space Institute, McGill University, 3550 rue University, Montréal, QC H3A 2A7, Canada
- ³⁰ Institut de Radioastronomie Millimétrique (IRAM), 300 rue de la Piscine, F-38406 Saint Martin d'Hères, France
- ³¹ Department of Astrophysics, Institute for Mathematics, Astrophysics and Particle Physics (IMAPP), Radboud University, P.O. Box 9010, 6500 GL Nijmegen, The Netherlands
- ³² Department of Astronomy, University of Massachusetts, 01003, Amherst, MA, USA
- ³³ Korea Astronomy and Space Science Institute, Daedeok-daero 776, Yuseong-gu, Daejeon 34055, Republic of Korea
- ³⁴ University of Science and Technology, Gajeong-ro 217, Yuseong-gu, Daejeon 34113, Republic of Korea
- ³⁵ Kavli Institute for Cosmological Physics, University of Chicago, 5640 South Ellis Avenue, Chicago, IL 60637, USA
- ³⁶ Department of Physics, University of Chicago, 5720 South Ellis Avenue, Chicago, IL 60637, USA
- ³⁷ Enrico Fermi Institute, University of Chicago, 5640 South Ellis Avenue, Chicago, IL 60637, USA
- ³⁸ Department of Space, Earth and Environment, Chalmers University of Technology, Onsala Space Observatory, SE-43992 Onsala, Sweden
- ³⁹ Princeton Center for Theoretical Science, Jadwin Hall, Princeton University, Princeton, NJ 08544, USA
- ⁴⁰ NASA Hubble Fellowship Program, Einstein Fellow
- ⁴¹ Data Science Institute, University of Arizona, 1230 N. Cherry Ave., Tucson, AZ 85721, USA
- ⁴² Program in Applied Mathematics, University of Arizona, 617 N. Santa Rita, Tucson, AZ 85721, USA
- ⁴³ Cornell Center for Astrophysics and Planetary Science, Cornell University, Ithaca, NY 14853, USA
- ⁴⁴ Shanghai Astronomical Observatory, Chinese Academy of Sciences, 80 Nandan Road, Shanghai 200030, People's Republic of China
- ⁴⁵ Key Laboratory of Radio Astronomy, Chinese Academy of Sciences, Nanjing 210008, People's Republic of China
- ⁴⁶ Physics Department, Fairfield University, 1073 North Benson Road, Fairfield, CT 06824, USA
- ⁴⁷ Department of Astronomy, University of Illinois at Urbana-Champaign, 1002 West Green Street, Urbana, IL 61801, USA
- ⁴⁸ Tsung-Dao Lee Institute, Shanghai Jiao Tong University, Shengrong Road 520, Shanghai, 201210, People's Republic of China
- ⁴⁹ Department of Astronomical Science, The Graduate University for Advanced Studies (SOKENDAI), 2-21-1 Osawa, Mitaka, Tokyo 181-8588, Japan
- ⁵⁰ Department of Astronomy and Columbia Astrophysics Laboratory, Columbia University, 550 W. 120th Street, New York, NY 10027, USA
- ⁵¹ Center for Computational Astrophysics, Flatiron Institute, 162 Fifth Avenue, New York, NY 10010, USA
- ⁵² Dipartimento di Fisica "E. Pancini," Università di Napoli "Federico II," Compl. Univ. di Monte S. Angelo, Edificio G, Via Cinthia, I-80126, Napoli, Italy
- ⁵³ INFN Sez. di Napoli, Compl. Univ. di Monte S. Angelo, Edificio G, Via Cinthia, I-80126, Napoli, Italy
- ⁵⁴ Wits Centre for Astrophysics, University of the Witwatersrand, 1 Jan Smuts Avenue, Braamfontein, Johannesburg 2050, South Africa
- ⁵⁵ Department of Physics, University of Pretoria, Hatfield, Pretoria 0028, South Africa
- ⁵⁶ Centre for Radio Astronomy Techniques and Technologies, Department of Physics and Electronics, Rhodes University, Makhanda 6140, South Africa
- ⁵⁷ ASTRON, Oude Hoogeveensedijk 4, 7991 PD Dwingeloo, The Netherlands
- ⁵⁸ LESIA, Observatoire de Paris, Université PSL, CNRS, Sorbonne Université, Université de Paris, 5 place Jules Janssen, F-92195 Meudon, France
- ⁵⁹ JILA and Department of Astrophysical and Planetary Sciences, University of Colorado, Boulder, CO 80309, USA
- ⁶⁰ National Astronomical Observatories, Chinese Academy of Sciences, 20A Datun Road, Chaoyang District, Beijing 100101, People's Republic of China
- ⁶¹ Las Cumbres Observatory, 6740 Cortona Drive, Suite 102, Goleta, CA 93117-5575, USA
- ⁶² Department of Physics, University of California, Santa Barbara, CA 93106-9530, USA
- ⁶³ National Radio Astronomy Observatory, 520 Edgemont Road, Charlottesville, VA 22903, USA
- ⁶⁴ Department of Electrical Engineering and Computer Science, Massachusetts Institute of Technology, 32-D476, 77 Massachusetts Ave., Cambridge, MA 02142, USA
- ⁶⁵ Google Research, 355 Main St., Cambridge, MA 02142, USA
- ⁶⁶ Institut für Theoretische Physik und Astrophysik, Universität Würzburg, Emil-Fischer-Str. 31, D-97074 Würzburg, Germany
- ⁶⁷ Department of History of Science, Harvard University, Cambridge, MA 02138, USA
- ⁶⁸ Department of Physics, Harvard University, Cambridge, MA 02138, USA
- ⁶⁹ NCSA, University of Illinois, 1205 W. Clark St., Urbana, IL 61801, USA
- ⁷⁰ Dipartimento di Fisica, Università degli Studi di Cagliari, SP Monserrato-Sestu km 0.7, I-09042 Monserrato, Italy
- ⁷¹ INAF—Osservatorio Astronomico di Cagliari, Via della Scienza 5, I-09047, Selargius, CA, Italy
- ⁷² Instituto Nacional de Astrofísica, Óptica y Electrónica. Apartado Postal 51 y 216, 72000. Puebla Pue., México
- ⁷³ Consejo Nacional de Ciencia y Tecnología, Av. Insurgentes Sur 1582, 03940, Ciudad de México, México

- ⁷⁴ Key Laboratory for Research in Galaxies and Cosmology, Chinese Academy of Sciences, Shanghai 200030, People's Republic of China
- ⁷⁵ NOVA Sub-mm Instrumentation Group, Kapteyn Astronomical Institute, University of Groningen, Landleven 12, 9747 AD Groningen, The Netherlands
- ⁷⁶ Department of Astronomy, School of Physics, Peking University, Beijing 100871, People's Republic of China
- ⁷⁷ Kavli Institute for Astronomy and Astrophysics, Peking University, Beijing 100871, People's Republic of China
- ⁷⁸ Department of Astronomy, Graduate School of Science, The University of Tokyo, 7-3-1 Hongo, Bunkyo-ku, Tokyo 113-0033, Japan
- ⁷⁹ The Institute of Statistical Mathematics, 10-3 Midori-cho, Tachikawa, Tokyo, 190-8562, Japan
- ⁸⁰ Department of Statistical Science, The Graduate University for Advanced Studies (SOKENDAI), 10-3 Midori-cho, Tachikawa, Tokyo 190-8562, Japan
- ⁸¹ Kavli Institute for the Physics and Mathematics of the Universe, The University of Tokyo, 5-1-5 Kashiwanoha, Kashiwa, 277-8583, Japan
- ⁸² Leiden Observatory, Leiden University, Postbus 2300, 9513 RA Leiden, The Netherlands
- ⁸³ ASTRAVEO LLC, P.O. Box 1668, Gloucester, MA 01931, USA
- ⁸⁴ Institute for Astrophysical Research, Boston University, 725 Commonwealth Ave., Boston, MA 02215, USA
- ⁸⁵ Astronomical Institute, St. Petersburg University, Universitetskij pr., 28, Petrodvorets, 198504 St. Petersburg, Russia
- ⁸⁶ Institute for Cosmic Ray Research, The University of Tokyo, 5-1-5 Kashiwanoha, Kashiwa, Chiba 277-8582, Japan
- ⁸⁷ Joint Institute for VLBI ERIC (JIVE), Oude Hoogeveensedijk 4, 7991 PD Dwingeloo, The Netherlands
- ⁸⁸ Department of Astronomy and Atmospheric Sciences, Kyungpook National University, Daegu 702-701, Republic of Korea
- ⁸⁹ Kogakuin University of Technology & Engineering, Academic Support Center, 2665-1 Nakano, Hachioji, Tokyo 192-0015, Japan
- ⁹⁰ Niigata University, 8050 Ikarashi-nino-cho, Nishi-ku, Niigata 950-2181, Japan
- ⁹¹ Physics Department, National Sun Yat-Sen University, No. 70, Lien-Hai Road, Kaosiung City 80424, Taiwan, R.O.C.
- ⁹² National Optical Astronomy Observatory, 950 N. Cherry Ave., Tucson, AZ 85719, USA
- ⁹³ Department of Physics, The Chinese University of Hong Kong, Shatin, N.T., Hong Kong
- ⁹⁴ School of Astronomy and Space Science, Nanjing University, Nanjing 210023, People's Republic of China
- ⁹⁵ Key Laboratory of Modern Astronomy and Astrophysics, Nanjing University, Nanjing 210023, People's Republic of China
- ⁹⁶ INAF-Istituto di Radioastronomia, Via P. Gobetti 101, I-40129 Bologna, Italy
- ⁹⁷ P. N. Lebedev Physical Institute of the Russian Academy of Sciences, 53 Leninskiy Prospekt, 119991, Moscow, Russia
- ⁹⁸ INAF-Istituto di Radioastronomia & Italian ALMA Regional Centre, Via P. Gobetti 101, I-40129 Bologna, Italy
- ⁹⁹ Department of Physics, National Taiwan University, No.1, Sect. 4, Roosevelt Rd., Taipei 10617, Taiwan, R.O.C
- ¹⁰⁰ Instituto de Radioastronomía y Astrofísica, Universidad Nacional Autónoma de México, Morelia 58089, México
- ¹⁰¹ Instituto de Astronomía, Universidad Nacional Autónoma de México (UNAM), Apdo Postal 70-264, Ciudad de México, México
- ¹⁰² Yunnan Observatories, Chinese Academy of Sciences, 650011 Kunming, Yunnan Province, People's Republic of China
- ¹⁰³ Center for Astronomical Mega-Science, Chinese Academy of Sciences, 20A Datun Road, Chaoyang District, Beijing, 100012, People's Republic of China
- ¹⁰⁴ Key Laboratory for the Structure and Evolution of Celestial Objects, Chinese Academy of Sciences, 650011 Kunming, People's Republic of China
- ¹⁰⁵ Anton Pannekoek Institute for Astronomy, University of Amsterdam, Science Park 904, 1098 XH, Amsterdam, The Netherlands
- ¹⁰⁶ Gravitation and Astroparticle Physics Amsterdam (GRAPPA) Institute, University of Amsterdam, Science Park 904, 1098 XH Amsterdam, The Netherlands
- ¹⁰⁷ Science Support Office, Directorate of Science, European Space Research and Technology Centre (ESA/ESTEC), Keplerlaan 1, 2201 AZ Noordwijk, The Netherlands
- ¹⁰⁸ School of Physics and Astronomy, Shanghai Jiao Tong University, 800 Dongchuan Road, Shanghai, 200240, People's Republic of China
- ¹⁰⁹ Institut de Radioastronomie Millimétrique (IRAM), Avenida Divina Pastora 7, Local 20, E-18012, Granada, Spain
- ¹¹⁰ Astronomy Department, Universidad de Concepción, Casilla 160-C, Concepción, Chile
- ¹¹¹ National Institute of Technology, Hachinohe College, 16-1 Uwanotai, Tamonoki, Hachinohe City, Aomori 039-1192, Japan
- ¹¹² South African Radio Astronomy Observatory, Observatory 7925, Cape Town, South Africa
- ¹¹³ Department of Physics, National and Kapodistrian University of Athens, Panepistimiopolis, GR 15783 Zografos, Greece
- ¹¹⁴ Villanova University, Mendel Science Center Rm. 263B, 800 E. Lancaster Ave., Villanova, PA 19085, USA
- ¹¹⁵ Physics Department, Washington University CB 1105, St. Louis, MO 63130, USA
- ¹¹⁶ Sejong University, 209 Neungdong-ro, Gwangjin-gu, Seoul, Republic of Korea
- ¹¹⁷ EACOA Fellow
- ¹¹⁸ Canadian Institute for Theoretical Astrophysics, University of Toronto, 60 St. George Street, Toronto, ON M5S 3H8, Canada
- ¹¹⁹ Dunlap Institute for Astronomy and Astrophysics, University of Toronto, 50 St. George Street, Toronto, ON M5S 3H4, Canada
- ¹²⁰ Canadian Institute for Advanced Research, 180 Dundas St. W, Toronto, ON M5G 1Z8, Canada
- ¹²¹ Radio Astronomy Laboratory, University of California, Berkeley, CA 94720, USA
- ¹²² Department of Physics, University College Cork, Kane Building, College Road, Cork T12 K8AF, Ireland
- ¹²³ Department of Physics, National Taiwan Normal University, No. 88, Sec. 4, Tingzhou Rd., Taipei 116, Taiwan, R.O.C.
- ¹²⁴ Center of Astronomy and Gravitation, National Taiwan Normal University, No. 88, Sec. 4, Tingzhou Road, Taipei 116, Taiwan, R.O.C.
- ¹²⁵ Finnish Centre for Astronomy with ESO, FI-20014 University of Turku, Finland
- ¹²⁶ Aalto University Metsähovi Radio Observatory, Metsähovintie 114, FI-02540 Kylmäla, Finland
- ¹²⁷ Gemini Observatory/NSF NOIRLab, 670 N. A'ohōkū Place, Hilo, HI 96720, USA
- ¹²⁸ Frankfurt Institute for Advanced Studies, Ruth-Moufang-Strasse 1, D-60438 Frankfurt, Germany
- ¹²⁹ School of Mathematics, Trinity College, Dublin 2, Ireland
- ¹³⁰ Department of Astrophysical Sciences, Peyton Hall, Princeton University, Princeton, NJ 08544, USA
- ¹³¹ Department of Physics, Tokyo Institute of Technology, 2-12-1 Ookayama, Meguro-ku, Tokyo 152-8551, Japan
- ¹³² Hiroshima Astrophysical Science Center, Hiroshima University, 1-3-1 Kagamiyama, Higashi-Hiroshima, Hiroshima 739-8526, Japan
- ¹³³ Aalto University Department of Electronics and Nanoengineering, PL 15500, FI-00076 Aalto, Finland
- ¹³⁴ Department of Astronomy, Yonsei University, Yonsei-ro 50, Soodaemun-gu, 03722 Seoul, Republic of Korea
- ¹³⁵ Department of Physics and Astronomy, Texas Tech University, Lubbock, TX 79409-1051, USA
- ¹³⁶ Netherlands Organisation for Scientific Research (NWO), Postbus 93138, 2509 AC Den Haag, The Netherlands
- ¹³⁷ Department of Physics and Astronomy, Seoul National University, Gwanak-gu, Seoul 08826, Republic of Korea
- ¹³⁸ University of New Mexico, Department of Physics and Astronomy, Albuquerque, NM 87131, USA
- ¹³⁹ Jeremiah Horrocks Institute, University of Central Lancashire, Preston PR1 2HE, UK
- ¹⁴⁰ Physics Department, Brandeis University, 415 South Street, Waltham, MA 02453, USA
- ¹⁴¹ Tuorla Observatory, Department of Physics and Astronomy, University of Turku, Finland
- ¹⁴² Radboud Excellence Fellow of Radboud University, Nijmegen, The Netherlands
- ¹⁴³ School of Natural Sciences, Institute for Advanced Study, 1 Einstein Drive, Princeton, NJ 08540, USA
- ¹⁴⁴ Princeton Gravity Initiative, Princeton University, Princeton, NJ 08544, USA
- ¹⁴⁵ School of Physics, Huazhong University of Science and Technology, Wuhan, Hubei, 430074, People's Republic of China
- ¹⁴⁶ Mullard Space Science Laboratory, University College London, Holmbury St. Mary, Dorking, Surrey, RH5 6NT, UK
- ¹⁴⁷ School of Astronomy and Space Sciences, University of Chinese Academy of Sciences, No. 19A Yuquan Road, Beijing 100049, People's Republic of China

¹⁴⁸ Astronomy Department, University of Science and Technology of China, Hefei 230026, People's Republic of China
¹⁴⁹ Bard College, 30 Campus Road, Annandale-on-Hudson, NY 12504, USA

Received 2022 March 10; revised 2022 April 7; accepted 2022 April 7; published 2022 May 12

Abstract

The extraordinary physical resolution afforded by the Event Horizon Telescope has opened a window onto the astrophysical phenomena unfolding on horizon scales in two known black holes, M87* and Sgr A*. However, with this leap in resolution has come a new set of practical complications. Sgr A* exhibits intraday variability that violates the assumptions underlying Earth aperture synthesis, limiting traditional image reconstruction methods to short timescales and data sets with very sparse (u, v) coverage. We present a new set of tools to detect and mitigate this variability. We develop a data-driven, model-agnostic procedure to detect and characterize the spatial structure of intraday variability. This method is calibrated against a large set of mock data sets, producing an empirical estimator of the spatial power spectrum of the brightness fluctuations. We present a novel Bayesian noise modeling algorithm that simultaneously reconstructs an average image and statistical measure of the fluctuations about it using a parameterized form for the excess variance in the complex visibilities not otherwise explained by the statistical errors. These methods are validated using a variety of simulated data, including general relativistic magnetohydrodynamic simulations appropriate for Sgr A* and M87*. We find that the reconstructed source structure and variability are robust to changes in the underlying image model. We apply these methods to the 2017 EHT observations of M87*, finding evidence for variability across the EHT observing campaign. The variability mitigation strategies presented are widely applicable to very long baseline interferometry observations of variable sources generally, for which they provide a data-informed averaging procedure and natural characterization of inter-epoch image consistency.

Unified Astronomy Thesaurus concepts: Galactic center (565); Black holes (162); Radio astronomy (1338); Very long baseline interferometry (1769); Time domain astronomy (2109); Astronomy data analysis (1858); Computational astronomy (293)

1. Introduction

The Event Horizon Telescope (EHT) is a global very long baseline interferometry (VLBI) array observing at a wavelength of ~ 1 mm, and it has been assembled with the primary goal of resolving the horizon-scale emission structures of both the M87* (Event Horizon Telescope Collaboration et al. 2019a, 2019b, 2019c, 2019d, 2019e, 2019f; hereafter M87* Papers I, II, III, IV, V, and VI, respectively) and Sgr A* (Event Horizon Telescope Collaboration et al. 2021c, 2022a, 2022b, 2022d, 2022e, 2022f; hereafter Papers I-VI, respectively) supermassive black holes (SMBHs). To date, all sources observed with the EHT during its 2017 campaign have been spatially resolved (Kim et al. 2020; Janssen et al. 2021), and many have exhibited structural variability across days. The most extreme of these variable sources is Sgr A*, which exhibits substantial variability across the electromagnetic spectrum (see, e.g., Boyce et al. 2019; Witzel et al. 2021; Wielgus et al. 2022, and references therein) and on horizon scales (see, e.g., Fish et al. 2011; Gravity Collaboration et al. 2018). The mass of Sgr A* is $M \approx 4 \times 10^6 M_{\odot}$ (Do et al. 2019; Gravity Collaboration et al. 2019, 2020), corresponding to a gravitational timescale of $t_g = GM/c^3 \approx 20$ s, which is much shorter than the ~ 10 hr duration of a typical EHT observing track.

Sources exhibiting substantial structural variability on timescales that are short compared to a VLBI observing track complicate the image reconstruction process. Because VLBI arrays have only sparse instantaneous coverage of the Fourier plane, standard practice is to use Earth-rotation aperture synthesis to improve the coverage by observing the source for several hours (Thompson et al. 2017); as the Earth rotates, so do

the baselines in the array, which therefore populate new regions of the Fourier plane. However, image reconstruction using data acquired via this technique assumes that the source remains static for the duration of the observation, such that the rotated baselines continue to sample the same source structure. For rapidly variable sources like Sgr A*, this assumption is broken.

The potential presence of short-timescale variability raises two distinct challenges: characterization and mitigation. The latter necessarily depends on the former; an appropriate mitigation scheme can only be selected after the properties of the variability have been identified. Methods to detect variability intrinsic to the source, and not imposed by subsequent atmospheric or station-induced corruptions, may be constructed using closure phases (Roelofs et al. 2017; Satpathy et al. 2022). However, the interpretation of such measures is complicated by the nontrivial relationship between closure phases and source structure.

We introduce an additional purely empirical method for detecting and, more importantly, characterizing structural variability based on visibility amplitudes. While this novel method must contend with systematic calibration uncertainties, the results may be immediately interpreted as the power spectrum of image fluctuations. This power spectrum naturally provides a prior on subsequent mitigation schemes.

There are at least three conceptually distinct approaches that have been applied (or proposed to be applied) for reconstructing variable sources from VLBI data:

1. The first approach—which we will refer to as the “snapshot reconstruction” approach—involves simply dividing the data into time segments that are short compared to the source variability timescale and then using standard reconstruction techniques. For sources whose variability timescales are longer than a few hours, the snapshot reconstruction approach is no different from multiepoch imaging, which has seen regular use in the



Original content from this work may be used under the terms of the [Creative Commons Attribution 4.0 licence](https://creativecommons.org/licenses/by/4.0/). Any further distribution of this work must maintain attribution to the author(s) and the title of the work, journal citation and DOI.

VLBI community to make movies of astronomical sources (e.g., Matthews et al. 2010; Lister et al. 2018; Walker et al. 2018; Kim et al. 2020).¹⁵⁰ However, for more rapidly variable sources the required data segmentation may lead to inadequate Fourier coverage that compromises image fidelity (e.g., Fomalont et al. 2001) or necessitates the use of restricted source models (e.g., Miller-Jones et al. 2019).

2. The second approach involves directly reconstructing a dynamic source model rather than a static one, and we will refer to this approach as “dynamical reconstruction.” We draw a distinction between dynamical reconstruction and snapshot reconstruction in that the former attempts to recover the time-continuous source structure, rather than restricting itself to static “frames” at the points in time where snapshot data are available. Example dynamical reconstruction algorithms include dynamical imaging (Johnson et al. 2017), StarWarps (Bouman et al. 2018), and RESOLVE (Arras et al. 2019, 2022), all of which impose some manner of temporal coherence or regularization on the reconstructed source structure. Such temporal regularization is necessary both to interpolate between times when data are present and to enforce structural continuity in time. In principle, this capability for data taken at one point in time to inform the image structure at another point in time should mean that dynamical reconstruction algorithms have less stringent requirements on dense instantaneous Fourier coverage than snapshot reconstruction algorithms do. But in practice, current dynamical reconstruction algorithms struggle in similar regimes of data sparsity to snapshot reconstructions (see Section 9 of Paper III).
3. The third approach is “visibility stacking,” whereby the source is observed over multiple epochs and the complex visibilities at each location in the Fourier plane are averaged in time. By the linearity of the Fourier transform, the image reconstructed from time-averaged visibilities should be the same as the average of images reconstructed from single-epoch visibilities, meaning that visibility stacking provides a method for recovering the average image structure from time-variable data. Lu et al. (2016) applied a visibility stacking technique, including light-curve normalization and temporal smoothing, to simulated EHT observations of Sgr A*, demonstrating that multiepoch averaging of the complex visibilities can substantially improve the reconstructed image fidelity compared to single-epoch imaging. However, such averaging requires access to calibrated visibilities, and in practice the visibility phases of EHT data are irretrievably corrupted by atmospheric effects (M87* Paper III).¹⁵¹

To this list we add a fourth approach: statistical reconstruction of the variability alongside static image reconstruction of the average source structure that may be deployed in Bayesian image reconstruction methods like those described in Broderick et al. (2020b) and Pesce (2021). Any variable structure can be

decomposed, without loss of generality, into a static (average) component and a dynamic (variable) component. If the duration of the observation is much longer than the variability timescale, then the variable component can be usefully conceptualized as defining a distribution from which the measured visibilities at any instant are drawn. If this distribution is parameterized and an appropriate likelihood function constructed, then the data can be used to simultaneously constrain both the parameters describing the variability and the average source structure. For EHT observations of Sgr A*, in which the observing window (~ 10 hr) is much longer than the expected variability timescale (\sim minutes), this statistical approach to source reconstruction in the face of variability is well motivated.

This paper is organized as follows: In Section 2 we provide a theoretical expectation for the variability behavior of EHT sources. In Section 3 we outline our proposed strategies for measuring and mitigating this variability during reconstruction. We describe a data-driven, model-agnostic procedure for characterizing and quantifying the amount of variability contained in the data in Section 4. In Section 5 we present an algorithm for simultaneously reconstructing both the average source structure and its parameterized variability. Both methods are demonstrated by application to the 2017 EHT M87* data in Section 6. Finally, we summarize and conclude in Section 7.

2. Expected Source Variability of EHT Targets

Structural variability in EHT observations of horizon-scale sources (i.e., Sgr A* and M87*) is anticipated to result from the turbulent physical processes associated with accretion and jet launching near the central black hole. Modeling these turbulent processes is currently performed via large-scale numerical computations, typically within the general relativistic magnetohydrodynamic (GRMHD) paradigm (see, e.g., M87* Paper V; Paper V, and references therein). These simulations may be post-processed through ray-tracing and radiative transfer computations to generate simulated images of the near-horizon emission regions (see, e.g., Gold et al. 2020, and references therein). Through this procedure, physically self-consistent and observationally credible predictions for the horizon-scale image structure and variability may be generated, from which the expected variability properties may be extracted. The resultant variability properties across the library of GRMHD simulations in Paper V are discussed in detail in Georgiev et al. (2022), and we only summarize them here.

We employ the library of simulation images constructed for EHT observations of Sgr A* to motivate the form of our variability mitigation strategy (Paper V). Each simulation generates a sequence of such images, or “movies.” These movies can be decomposed into a mean image and movie of random brightness fluctuations, both of which are of intrinsic interest for EHT sources. The spatial power spectrum density (PSD) of the brightness fluctuations are computed and presented in Georgiev et al. (2022), which finds that they are universally well characterized by a “red–red” noise process. That is, the largest brightness fluctuations typically occur on the longest timescales and the largest spatial scales.

This procedure can be repeated for movies of different temporal lengths, generating families of PSDs that are indicative of the fluctuation spectra over the different observationally relevant timescales. In all cases, the PSDs are

¹⁵⁰ For a large compendium of VLBI movies of active galactic nuclei, see www.physics.purdue.edu/MOJAVE.

¹⁵¹ It may be possible to retrieve some phase information through phase precalibration procedures (e.g., self-calibrating to a fiducial source structure) or the use of closure phases (see, e.g., Roelofs et al. 2021). We leave a full exploration of these possibilities for future work.




Figure 1. Summary of the (u, v) -coverage across the four observation days, including both high and low bands, in the 2017 Sgr A* EHT campaign. Radii of constant baseline length are shown by the dashed gray circles.

well described by a broken power law in spatial frequency,¹⁵² and therefore in baseline length, $|u|$. The location of this break ranges from $u_0 \sim 1$ to $3 \text{ G}\lambda$, corresponding to angular scales ranging from 70 to $200 \mu\text{as}$ and associated with the typical extent of the emission within the image. For $|u| < u_0$, the PSD asymptotes to a constant. For averaging times $T \gtrsim 10^3 \text{ GM}/c^3$ the spatial PSDs are independent of T , indicating the lack of correlated variability on longer timescales in most simulations. For Sgr A* and M87*, $10^3 \text{ GM}/c^3$ corresponds roughly to 5.5 hr and 1 yr , respectively. For averaging times shorter than this timescale, the maximum of the PSD decreases roughly $\propto T^{2-3}$ and the location of the break increases.

The variability in the brightness fluctuations can be substantially reduced by normalizing the visibility data by the total flux light curve. This leverages the “red–red” nature of the brightness fluctuations and explicitly eliminates the variability on zero baselines. Because variability on $|u| < u_0$ is correlated with that at zero baselines, this light-curve normalization reduces a significant fraction of the additional variability on nonzero baselines shorter than the break. Generically, at small $|u| \lesssim u_0$ the PSDs of the light-curve-normalized brightness fluctuations scale as $|u|^{2-4}$, depending on the assumed calibration details. For $|u| \gtrsim u_0$, the PSDs generally fall with power-law indices of $2-3$.

For GRMHD simulations viewed from close to the polar axis the PSDs are approximately azimuthally symmetric. However, for simulations of accretion flows that are viewed nearly edge-on, which exhibit significant departures in azimuthal symmetry in their images, the PSD at $4 \text{ G}\lambda$ can vary by as much as 50% . Nevertheless, we will proceed with the approximation that the PSDs are functions of $|u|$ alone, subject to the validation experiments performed in the following sections.

3. Summary of Intraday Variability Mitigation Strategy

Intraday variability presents a substantial challenge for VLBI generally, and especially so for that performed by the EHT specifically, which has sparse (u, v) -coverage, as shown in Figure 1. Methods that attempt image reconstruction and model-based parameter inference from the 2017 EHT observations of Sgr A* using segments of the data that span time ranges

shorter than that associated with the variability must contend with at least two significant challenges:

1. A dramatically reduced data volume. Limiting the segmentation time to minutes reduces the number of independent VLBI (non-intrasite) measurements to 15 in the best case, in comparison to the many hundreds obtained throughout a night owing to Earth aperture synthesis. As a direct consequence, the number of independent parameters that can be effectively constrained is drastically limited.
2. The inherent complexity and stochasticity of the anticipated variability, based on the turbulence observed in GRMHD simulation movies.

The strategy presented here is to statistically address the putative variability so that standard VLBI analysis tools that leverage Earth aperture synthesis can still be applied despite the presence of significant intraday variability. In this sense, the properties of the average brightness distribution are simultaneously measured with their covariance, or “noise,” over the observation window. This procedure is formally equivalent to marginalizing over realizations of the noise and is statistically well justified when the timescale of the variability is short in comparison to the observing window.

The additional variability-induced noise is an addition to, not a replacement for, the usual measurement uncertainties. Thermal noise is the dominant contribution to these uncertainties and is dependent solely on the telescope operations at individual sites, such as system temperature, bandwidth, integration time, etc. (Thompson et al. 2017). To a very good approximation, the thermal errors on the real and imaginary components of the complex visibilities are Gaussian. We will assume that thermal error is synonymous with the statistical error, which may include small additional contributions from phasing efficiency, phase coherence, etc. Importantly, these errors are independent for each measurement, known a priori, and insensitive to the intrinsic source structure and its variability.

This strategy comes with its own set of challenges. Typically, there is not a single variability timescale, but rather a variability spectrum, with some components of the variability appearing well within the observing window and others extending beyond it. This multitude of timescales is evident, e.g., in the variability properties of the light curve of Sgr A* during the 2017 EHT observations (Wielgus et al. 2022) and suggested by the GRMHD simulations described in the

¹⁵² For interferometric observations, such as those performed by the EHT, when measured in λ the baseline lengths are directly proportional to the spatial frequency within the image domain. Thus, individual observations directly probe the Fourier transform of the image at specific spatial frequencies set by the baseline.

previous section (Georgiev et al. 2022). More important is the presence of correlations between measured visibilities, which will be present even in the absence of spatial correlations in the image. These correlations complicate the manner in which the noise is introduced.

In practice, we generate a model of the diagonal elements of the covariance that incorporates the additional deviations of the complex visibilities from a mean image that result from the structural variability within the source. These variances can be estimated directly from the data (Section 4) or obtained simultaneously with model comparisons and image reconstructions (Section 5). In the remainder of this section we discuss how correlations on different scales are addressed and the procedures we present in this paper are validated.

3.1. Large-scale Correlations

The light curve of Sgr A* during the observing nights throughout the 2017 EHT campaign is dominated by fluctuations on the longest timescales (Paper V; Wielgus et al. 2022). This is consistent with other studies that cover much longer time spans, which suggest a potential break at a timescale between 2 and 8 hr (Dexter et al. 2014; Witzel et al. 2018, 2021).

This temporal behavior is consistent with the expectations from GRMHD simulations, described in Section 2 and reported in detail in Georgiev et al. (2022). Within the GRMHD simulations, the long-timescale variability is associated with variations in the largest-scale features of the image. In this sense, the spatiotemporal power spectrum is “red–red,” i.e., the largest-amplitude fluctuations in the source brightness occur on the longest timescales and largest spatial scales. As a direct result, the largest correlations are driven by the longest temporal/largest spatial fluctuations.

We remove these a priori by light-curve-normalizing the visibility data. By construction, the normalized data have vanishing variance at zero baseline. For GRMHD simulations, the suppression of fluctuation power extends to $|u| \approx 2 G\lambda$ (Georgiev et al. 2022). A direct consequence of this procedure is that the reconstructed variance is unable to address these omitted long temporal/large spatial scale modes.

3.2. Small-scale Fluctuations

GRMHD simulations exhibit turbulence in the emitting plasma, leading to short-time/small-scale stochastic fluctuations in the images (M87* Paper V; Paper V). These occur on all scales, ranging from the field of view of the EHT observations ($\gtrsim 200 \mu\text{as}$) to well below the formal resolution of the EHT ($\lesssim 20 \mu\text{as}$; Georgiev et al. 2022). These structural fluctuations are the source of the additional noise that the mitigation scheme presented here is addressing.

3.3. Methodology, Caveats, and Validation

The adopted methods only model the diagonal elements of the covariance of the complex visibility data associated with the underlying structural variability, thereby leaving out correlations. The largest correlations are avoided by fitting to light-curve-normalized complex visibilities. Nevertheless, other correlations including the short-time/small-scale fluctuations are not directly addressed, and we have no a priori reasons to believe that they are negligible. Indeed, in Section 4 we see clear evidence for the existence of nontrivial correlations.

The implication of these residual correlations for the fidelity of image reconstructions and parameter estimates is not immediately clear. Thus, we specified the following set of validation experiments, applied where possible to the specific observation parameters (e.g., (u, v) -coverage, observation times) relevant for the analysis in question:

1. Demonstrated on simulated data sets with Gaussian noise added to individual complex visibility estimates.
2. Demonstrated on simulated data sets with Gaussian noise fluctuations with a specified power spectrum overlaid on the image. These are uncorrelated in the image domain but will have residual correlations in the (u, v) -domain owing to the finite source size.
3. Demonstrated on simulated data sets in which structural brightness fluctuations are added via the `iNoisy` prescription in a manner that is spatially correlated in the image domain (Lee & Gammie 2021).
4. Demonstrated on simulated data sets generated from imaging GRMHD simulations. Fluctuations are necessarily correlated in the image domain in a manner that reflects the self-consistent physical evolution of the emission region.

These experiments are progressive in that additional complications, related to the nature and strength of correlations, are incorporated in subsequent experiments. Thus, we treat them as cumulative: successful validation using GRMHD simulations implies a successful validation using the `iNoisy` sets, etc.

All methods presented here are successfully validated via multiple of the above experiments, including on simulated data sets produced from GRMHD simulations.

4. Data-driven Characterization of Variability

VLBI data sets collected over many observation epochs contain within them a natural characterization of source variability (see Figure 1). We exploit this feature in the 2017 EHT observing campaign to assess the magnitude and spectrum of the intrinsic source variability.

Data sets that may be combined include those taken on multiple days, crossing tracks in the (u, v) -plane throughout the night, and multiple observation bands (e.g., low- and high-band EHT data) where the spectral dependence of the source may be neglected across them. Additionally, lower limits on the intrinsic source size, α , induce correlation in the (u, v) -plane, meaning that neighboring points in the (u, v) -plane may also be compared. Expressed in EHT-relevant units, the typical distance within the (u, v) -plane over which the complex visibilities are strongly correlated is $\Delta u \approx 1.0(\alpha/200 \mu\text{as})^{-1} G\lambda$. Within this scale, independent of the small-scale structure within the image, we may treat the visibilities as sampling similar aspects of the intrinsic source structure. In practice, we assume that the structure of the visibility may be modeled by a linear function within patches of this size, with the remaining suprathreshold variations indicative of the combination of structural variability, refractive scattering, and residual systematic uncertainty.

Therefore, the strategy for obtaining a model-agnostic, data-driven characterization of variability at any given point in the (u, v) -plane (u_0, v_0) is as follows:

1. Select all data points across all relevant days and bands within a silo of diameter $\Delta u = 1 G\lambda$ about (u_0, v_0) .

2. Detrend the selected data points with a linear model in (u, v) to disentangle the gross source structure from the fluctuations about it.
3. Compute debiased estimates of the mean of the trend and the variance of the residuals.
4. Average these estimates in azimuth.

The final step reduces the statistical uncertainty in the mean and variance, addresses sparse (u, v) -coverage, and facilitates direct comparisons with Section 2.

Insofar as the above strategy provides a measure of the variability in excess to that anticipated by the thermal errors, including the potential temporal correlations, it is directly comparable to the additional uncertainty required to fit static models to variable data sets. An additional debiasing step that addresses temporal correlations, necessary to compare with theoretical expectations of the power spectrum of visibility amplitude fluctuations, is described in Section 4.5.

4.1. Data Selection

To avoid having to address the unknown station phase delays, i.e., an inherently uncertain self-calibration procedure in the absence of a known source model, we employ the visibility amplitudes. Visibility amplitudes constructed from complex visibilities with Gaussian (thermal) noise are distributed according to the Rice distribution, which is only approximately Gaussian. In the following analysis we therefore restrict our attention to scan-averaged data values and data points for which the signal-to-noise ratio is $S/N \geq 2$, where the Rice distribution is approximated well by a Gaussian.

We combine the data sets from high and low bands, centered on 227.1 and 229.1 with 2 GHz bandwidths, and across all observation times, including through and across observation nights. All data are equally weighted, i.e., we do not attempt to address the different number and quality of data on different days. This combined data set is assumed to provide an ensemble of comparable observations from which we may estimate the desired statistical properties.

Station gains impose an important potential additional systematic uncertainty. In most cases, we marginalize over the credible range of station gains (see Section 4.3). However, there are two important preprocessing steps that we employ to reduce the impact of gain errors within the 2017 EHT observation campaign.

First, we employ the network calibration procedure described in M87* Paper II to set the gain amplitudes at JCMT, SMA, ALMA, and APEX to within 1%.

Second, we calibrate the LMT gain amplitudes by fixing the visibility amplitudes on the LMT-SMT baseline to a Gaussian model, with an FWHM of $60 \mu\text{as}$, comparable to the second-moment estimates of M87* and Sgr A*. This does not eliminate uncertainty in the LMT gains, but rather reduces it to a combination of that associated with the SMT and the error in the applicability of the Gaussian model, eliminating the large potential swings (see, e.g., Figure 34 of M87* Paper IV). This calibration procedure does, however, artificially suppress the variance on baselines shorter than $2 G\lambda$, and thus we will focus our attention only on baselines long enough to be unaffected by the calibration procedure.

Third, to avoid significant losses on JCMT associated with poor phase coherence during scan averaging, prior to

coherently averaging we phase-calibrate the JCMT to a point-source model.

4.2. Estimating Statistical Properties of a Single Patch

We begin with estimating the mean and variance of the visibility amplitudes within a radius $\Delta u/2$ of some point (u_0, v_0) within the (u, v) -plane, which we refer to as a ‘‘patch.’’ Such estimates may be constructed at any point in the (u, v) -plane where a sufficient number of visibility amplitudes exist, i.e., $N \geq 4$. For $\Delta u = 1 G\lambda$, given the 2017 Sgr A* EHT campaign coverage, there are roughly 60 independent patches within $|u| = 9 G\lambda$ containing sufficient data to generate local mean and variance estimates.

4.2.1. Detrending Visibilities

The visibility amplitudes within a patch will vary as a result of both variability and intrinsic structure. Because it is the former that is of interest here, to exclude the latter, we first estimate the linear trend across the patch. As long as Δu is sufficiently small, a linear model is an excellent approximation of the average visibility amplitudes across the patch.

The linear model is defined by $V(u, v) = \bar{V} + V_u(u - u_0) + V_v(v - v_0)$. The detrending procedure is described in Appendix A. The reconstructions of the detrending parameters, \bar{V} and (V_u, V_v) , are unbiased for Gaussian errors on the amplitudes. The fidelity of the trend reconstruction depends on the number and S/N of the amplitudes. Having chosen $(\bar{u}, \bar{v}) = (u_0, v_0)$ makes no significant change to the trend reconstruction.

The outputs of this procedure are the mean amplitude within the patch, estimated at the patch center, \bar{V} , and the detrended amplitudes within the patch, $\hat{V}_j = V_j - V(u_j, v_j)$. This is supplemented with the thermal errors at those locations, $\sigma_{\text{th},j}$.

4.2.2. Statistical Estimators

Inherent within the detrended ensemble, $\{\hat{V}_j\}$, is an estimate of the statistical properties of the structural fluctuations not accounted for by the linear trend. These are necessarily biased by the thermal fluctuations and structural variations, both of which must be removed.

We estimate the debiased variance by

$$\sigma^2 = \frac{1}{N-3} \sum_j \max(\hat{V}_j^2 - \sigma_{\text{th},j}^2, 10^{-2}\sigma_{\text{th},j}^2), \quad (1)$$

which includes a cutoff at $10^{-2}\sigma_{\text{th},j}^2$ to avoid pathologies associated with ‘‘over-debiasing,’’ in which statistical fluctuations below $\sigma_{\text{th},j}^2$ generate negative estimates of σ^2 . The normalization of $N-3$ is a consequence of having three degrees of freedom in the linear detrending model.

The debiased estimate of the mean is given by

$$\mu^2 = \max\left(\bar{v}^2 - \sigma^2 - \frac{1}{N} \sum_j \sigma_{\text{th},j}^2, 0\right), \quad (2)$$

where the mean estimate from the linear detrending procedure is corrected for the biases arising from the thermal and structural fluctuations, characterized by the patch variance estimate.

To demonstrate these estimates, we generate a simple simulated data set composed of 10 complex visibilities, V_j ,

located at (u, v) -positions (u_j, v_j) randomly selected about a center (u_0, v_0) . At each (u_j, v_j) , the V_j is generated from a fixed linear model with $\hat{V} = 1$, $V_u = 0.5$, $V_v = 0$, and two complex zero-mean Gaussian random fluctuations, one representing the thermal uncertainty and the other the structural variability, both with amplitude 0.1. Repeating this procedure, holding the linear model and (u, v) -positions fixed, produces an ensemble of data sets, from which the distributions of the reconstructed μ and σ^2 are shown in red in Figure 2.

The estimate of μ is unbiased, with an accuracy that depends on the degree of variability and number of visibility amplitudes. Even when only four points are used, this quantity is reasonably well behaved, appearing normal and centered on the “truth” value.

The distribution of the estimated variance is clearly not normal, matching a lognormal distribution more closely. The specific realization of the (u_j, v_j) does impact the distribution, with the degree of impact increasing as the number of amplitudes included decreases. When the impact of the structural variability is much smaller than the thermal errors, i.e., $\sigma \ll \sigma_{\text{th}}$, the variance estimate can be inaccurate.

4.2.3. Error Estimates

We estimate the errors on the estimates μ and σ^2 for a single patch via a Monte Carlo procedure, Monte Carlo Errors (MCEs), that may be applied to the data directly. Doing so avoids the need to propagate the individual thermal errors through the detrending procedure and, as done in the following sections, include additional sources of uncertainty (e.g., gain uncertainties, polarization leakage). This process begins with generating an ensemble of data sets produced by introducing two additional complex, zero-mean, unit-variance Gaussian random variables, x_j and y_j :

$$V'_j = |V_j + \sigma_{\text{th}}x_j + \sigma y_j|, \quad (3)$$

where σ^2 is the variance estimate from the observations. This procedure presumes that the thermal noise on the complex visibilities is Gaussian (well justified) and that the structural variations are independent (perhaps not well justified). Each generated set of V'_j is analyzed in a fashion identical to that described above: detrended, and μ and σ^2 estimated from Equations (2) and (1), respectively.

These must be further debiased to remove the impact of the original fluctuations inherent in the amplitude data. Therefore, we generate an ensemble of estimates that are further debiased via

$$\begin{aligned} \sigma'^2 &= \max \left[\sigma^2(V'_j) - \frac{1}{N-3} \sum_j \sigma_{\text{th},j}^2 - \sigma^2(V_j), 0 \right] \\ \mu'^2 &= \max \left[\mu^2(V'_j) - \frac{1}{N} \sum_j \sigma_{\text{th},j}^2 - \sigma^2(V_j), 0 \right]. \end{aligned} \quad (4)$$

The distribution of estimates from the MC ensemble is shown in blue in Figure 2. For both μ and σ^2 , the MCE distributions are quantitatively similar to those generated from ensembles of simulated data. This similarity extends for σ^2 to being biased toward large values. The additional debiasing, which eliminates the double counting of the induced and original fluctuations, does indeed appear to satisfactorily remove any residual offsets between the true and reconstructed distributions.




Figure 2. Distributions of the mean and variance reconstructions for a specific realization of the (u, v) -positions of simulated data points with thermal and structural variability included. In red, the distributions from an ensemble of such experiments are shown, holding the underlying mean visibility map and (u, v) positions fixed. The truth values are indicated by the vertical black lines. The average mean and variance are indicated by the vertical solid red lines. The vertical dashed red line shows the average log variance. The gray shaded region indicates the region in which the noise is subthermal. The vertical dashed blue lines indicate the μ and σ^2 from the data realization used to generate the bootstrap error estimates, shown by the blue distributions and with means shown by the blue solid lines.

We reiterate that this MCE procedure has the considerable virtue of being applicable to the actual data, providing a credible means by which to assign uncertainties to the patch-specific means and variances.

4.3. Azimuthally Averaged Statistical Properties

The procedure outlined above may be used to produce estimates of the variance arising from structural variations in the source throughout the (u, v) -plane. However, in many instances, and explicitly for the 2017 EHT observations (M87* Paper III), the baseline coverage is very sparse. Combined with the expectation that the power spectrum of the structural variability is only modestly dependent on position angle, this sparsity motivates the construction of azimuthally averaged estimates of μ and σ^2 , which are then functions of only the baseline length.

4.3.1. Averaged Statistical Estimators

To generate these, we first produce a polar grid of patch centers. In these the radial positions, ρ_s , are linearly spaced with separation $\Delta u/2$, so that neighboring patches overlap.¹⁵³

¹⁵³ In what follows (s, t) correspond to the radial and azimuthal patch indices to differentiate them from j , by which we index individual data points.




Figure 3. Locations of circular patches in the (u, v) -plane within which means and variances of the detrended data are computed. For reference, the locations of the 2017 EHT Sgr A* measurements are indicated in blue. Red patches contain more than four data points and therefore contribute to the azimuthally averaged statistical estimates; open gray patches do not contribute.

At each radial position, a set of azimuthal positions ϕ_{st} are chosen so that azimuthal spacing is $\leq \Delta u/2$. These then provide a set of $(u_0, v_0)_{st} = (\rho_s \cos \phi_{st}, \rho_s \sin \phi_{st})$. At each polar patch position, we generate estimates of the mean and variance of the detrended visibility amplitudes, μ_{st} and σ_{st}^2 . The location of these patches is illustrated in Figure 3. Each data point will contribute to multiple patches.

Azimuthally averaged quantities are generated by weighting each patch’s estimate by the numbers of degrees of freedom. The resulting azimuthally averaged estimate of the mean is given by

$$\mu_s = \frac{\sum_t (N_{st} - 3) \mu_{st} \Theta(N_{st} - 3)}{\sum_t (N_{st} - 3) \Theta(N_{st} - 3)}, \quad (5)$$

where $\Theta(x)$ is the standard Heaviside function. Because the variance estimates appear to be lognormal, and thus vary over many orders of magnitude, we average $\log(\sigma^2)$, i.e.,

$$\log(\sigma_s^2) = \frac{\sum_t (N_{st} - 3) \log(\sigma_{st}^2) \Theta(N_{st} - 3)}{\sum_t (N_{st} - 3) \Theta(N_{st} - 3)}. \quad (6)$$

Note that this estimate of σ_s^2 emphasizes those patches that have many data points and therefore are likely to be more accurate.

4.3.2. Averaged Error Estimates

Neighboring grid points are not necessarily independent, and thus the uncertainty in the combination is expected to be significantly larger than would be inferred if they were. Therefore, the Monte Carlo estimates of the error in μ_s and σ_s^2 must be performed after the azimuthal averaging. Residual gain errors present an additional source of uncertainty on the reconstructed means and variances. Therefore, the MCEs for the azimuthally averaged data sets follow a similar but distinct procedure to that for the individual patches.

We begin by constructing estimates of μ_s and σ_s^2 . With these, we generate an ensemble of data sets as described by Equation (3). Each ensemble element is subsequently modified by introducing gain amplitude fluctuations, introducing a correlated fluctuation across the data set. For application to the 2017 EHT Sgr A* campaign, we adopt gain uncertainties consistent with those reported in Paper III. For sites for which network calibration is performed (ALMA, APEX, JCMT, and SMA) we assume a gain amplitude error of 1%; all other sites are assigned a gain amplitude error of 10%. These additional gain fluctuations are assumed to be normally distributed and applied on a per-scan basis. Finally, we normalize the ensemble data by the correlated flux on the intrasite baselines (ALMA-APEX, JCMT-SMA) as an approximation to the light curve.

4.3.3. Estimating Noise Model Parameters

We ultimately seek to compare the empirical noise estimates with those found in GRMHD simulations by Georgiev et al. (2022). To facilitate this comparison, we fit the azimuthally averaged σ_s^2 with a broken power-law model, consistent with that found to be applicable to GRMHD simulations:

$$n(|u|) = \frac{a^2 (|u|/u_0)^c}{1 + (|u|/u_0)^{b+c}}. \quad (7)$$

Because the azimuthally averaged variance estimates are approximately lognormal, we perform this fit on the logarithm of the reconstructed σ_s^2 .

We find that the variance estimates themselves are susceptible to correlated errors, presumably due to the correlations in the fluctuations induced by noise imposed within the image domain. Therefore, we inflate the MCE estimates on the σ_s^2 by a factor of two, which safely encapsulates the discrepancy in the numerical validation experiments described in the following sections. In summary, the log-likelihood explored is

$$\mathcal{L} = -\sum_s \frac{\{\log(\sigma_s^2) - \log[n(\rho_s)]\}^2}{8(\text{err}_s/\sigma_s^2)^2}, \quad (8)$$

where err_s is the geometric mean of two-sided 1σ quantiles from the MCE ensemble for σ_s^2 .

The noise model parameters, $\{a, u_0, b, c\}$, are estimated by sampling this likelihood using the Python-based ensemble Markov Chain Monte Carlo package `emcee` (Foreman-Mackey et al. 2013). Typically, 10^5 steps are taken by 128 walkers, of which 10^4 are randomly selected in the latter half of the ensemble of chains. Beyond this point, the joint posteriors of all of the noise parameters are insensitive to the number of MCMC steps taken.

4.4. Validation

We explore a number of validation exercises that follow the validation ladder laid out in Section 3. In summary, within the region for which we expect high-fidelity characterization of the structural variation, we find that we are able to do so. This encompasses the baselines such that $2 G\lambda < |u| < 6 G\lambda$, where baselines shorter than $2 G\lambda$ are excluded by the LMT calibration procedure, and at baselines longer than $6 G\lambda$ the structural variability is subdominant to the thermal noise.

In each validation exercise, the simulated data sets were processed as described in Section 4.1. That is, (1) they are




Figure 4. Data-driven estimates of the mean and variance for simulated data sets generated using the 2017 EHT Sgr A* campaign parameters assuming the scattered *iNoisy* crescent, double point source, and elliptical disk models from Paper III. Gray triangles show an estimate of the thermal noise in each radial baseline bin. The time- and azimuthally averaged visibility amplitudes and temporal variances associated with the idealized visibility functions of the input movies are shown for each of the four observation days by the red lines. The orange shaded region indicates the 95% confidence level region spanned by the broken power-law fit to the variance between 2.5 and 6 $G\lambda$ described in Section 4.3.3. For reference, the visibility amplitudes of the 60 μs FWHM Gaussian that was used to provide an intermediate calibration of the LMT as described in Section 4.1 are shown by the blue dashed lines.

network calibrated, and light-curve normalized using the intrasite fluxes (ALMA-APEX and JCMT-SMA) interpolated to intermediate scans as required; (2) the complex LMT gains are set by calibrating to a 60 μs FWHM Gaussian; and (3) JCMT is phase-calibrated to a point source.

The resulting data sets are then analyzed as described above with $\Delta u = 1 G\lambda$. Note that we show results for baseline length spacing of 0.5 $G\lambda$, and thus subsequent values are formally correlated.

These are compared to the azimuthally averaged mean and variance of the visibilities computed directly from “truth” movies, without any attempt to restrict them to any subset of the (u, v) -plane, that is, without any of the constraints imposed by the actual observations.

4.4.1. *iNoisy* Validation Results

The images used as part of the validation scheme for the various image reconstructions in Paper III provide a natural set of simple examples in which the fluctuations are introduced in the image domain. In each, a geometric brightness map is modified by the imposition of a set of correlated fluctuations via the *iNoisy* prescription, in which a set of temporally and spatially correlated brightness fluctuations are constructed in a fashion that mimics the turbulent structures within accretion disks (Lee & Gammie 2021).

This *iNoisy* method provides substantial control over the properties of the image variability while separating it from the complexity of the source structure. The structural variability induced by *iNoisy* in these images is tuned to match that exhibited by Sgr A*, as measured by the light curve and variations in the closure phase as quantified via the Q -metric, a noise-weighted measure of the closure phase variability described in Roelofs et al. (2017). The construction of the simulated *iNoisy* data sets is described in detail in Section 5

of Paper III. However, the apparent spatial correlations are typically confined to smaller scales than those characteristic of the geometric model.

The *iNoisy* data sets that we employed during the validation of the statistical estimators include a crescent, ring, double source, simple disk, elliptical disk, and ring with a 30-minute-period hot spot (see Paper III for further details). Each “truth” movie was resampled on each of the 4 days with different thermal noise, complex gain, scattering, and structural fluctuation realizations. Three examples—the crescent, point source, and elliptical disk—are shown in Figure 4.

In all cases, the estimated azimuthally averaged mean and variance maps match those associated with the “truth” movies well. The LMT calibration procedure does produce artifacts at $|u| \lesssim 2.5 G\lambda$, extending marginally above that. This is especially visible in the estimated variances. However, it is also visible in the estimated means, which hew closely to the 60 μs FWHM Gaussian assumed during the LMT calibration.

For $|u| \gtrsim 6 G\lambda$, the structural variability is modestly subdominant to the thermal errors, indicated by their average values. As anticipated, there are modest departures from the truths in this region.

The consistency extends to the range of fit broken power-law noise models. Because the break in the truth variances occurs below $|u| \approx 2.5 G\lambda$, there is little traction on the break location and the short-baseline power-law index. However, both the overall amplitude and long-baseline power-law index are well constrained.

4.4.2. GRMHD Validation Results

GRMHD simulations provide a credible proxy for source structure of astronomical sources on horizon scales (Paper V; Georgiev et al. 2022). While there is a limited range of potential image morphologies within the GRMHD libraries,




Figure 5. Data-driven estimates of the mean and variance for simulated data sets generated using the 2017 EHT Sgr A* campaign parameters assuming three different GRMHD simulations from the validation set used in Paper IV. Gray triangles show an estimate of the thermal noise in each radial baseline bin. The time- and azimuthally averaged visibility amplitudes and temporal variances associated with the idealized visibility functions of the input movies are shown for each of the four observation days by the red lines. The orange shaded region indicates the 95% confidence level region spanned by the broken power-law fit to the variance between 2.5 and 6 Gλ described in Section 4.3.3. For reference, the visibility amplitudes of the 60 μ s FWHM Gaussian that was used to provide an intermediate calibration of the LMT as described in Section 4.1 are shown by the blue dashed lines. Note that the vertical axis range of the bottom row differs from that in Figure 4, reflecting the greater degree of variability in the GRMHD simulations.

they do provide a physically motivated and self-consistent set of intensity fluctuations. Importantly, these models exhibit the spatial and temporal correlations that are anticipated in accreting and jet-launching environments.

Each “truth” movie was resampled with (u, v) -coverage identical to that of Sgr A* during the 2017 EHT campaign on each of the four observation days with different realizations of thermal noise, complex gain, and scattering. The simulated data sets share many of the features of those associated with the *iNoisy* sets: the images are complex, contain significant image-domain correlations that translate into corresponding visibility-domain correlations, and contain an underlying noise spectrum that is not known a priori. The latter fact motivates a comparison to the data-driven nonparametric estimates from Section 4.

However, the GRMHD simulation data sets do differ in two important respects. First, they exhibit a much wider array of behaviors, extending from small-scale fluctuations like those in the *iNoisy* sets to large-scale arcing structures that differ from the *iNoisy* images. These arcing features induce long-timescale correlations that are not otherwise present in the *iNoisy* sets. Second, there is no attempt to restrict the simulations to those that reproduce the variability observed in Sgr A*. As a result, the variability present in the GRMHD simulations is typically larger than that exhibited by Sgr A* (Paper V).

Three typical GRMHD validation examples are shown in Figure 5. As with the *iNoisy* validation examples, this example accurately reconstructs the underlying truth variances associated with the full GRMHD movie for $2.5 \text{ G}\lambda < |u| < 6 \text{ G}\lambda$, limited at shorter baselines by the LMT calibration procedure and at larger baselines by the thermal noise.

These are representative of 100 such GRMHD simulation comparisons.

As with the *iNoisy* models, the break in the truth variances occurs below $|u| \approx 2.5 \text{ G}\lambda$, and therefore only the overall amplitude and long-baseline power-law index are well constrained.

4.5. Debiased Variability Measurement

Thus far, no attempt has been made to address clear artifacts in the normalized variance estimates in the examples shown in Figures 4 and 5 that are due to unaddressed temporal correlations in the simulated data sets. These correlations are real and anticipated in the actual Sgr A* data, arising from the fact that on a single night neighboring positions in the (u, v) -plane are observed at nearby times. Insofar as the variance estimate is used to quantify the excess noise required to accommodate fitting to stationary models (including images, geometric models, and physical models) to data sets composed of a full observation night, the prior scheme is sufficient. However, it is possible to envision a debiasing procedure in which these correlations are corrected, which we present here.

The temporal-correlation artifacts are most prominent between 6 and 7.5 Gλ, within which, for every example case shown in Figures 4 and 5, the normalized variance estimates exhibit a deficit of variability. This range of baseline lengths is especially sparsely sampled by the 2017 Sgr A* baseline coverage, with only one baseline contributing on most days (see Figure 1). For models in which the stochastic image fluctuations exhibit red temporal power spectra, as anticipated by GRMHD models of Sgr A* and observed in the light curve of Sgr A*, this sparsity implies a strong correlation among the visibility amplitudes within (u, v) -bins within this baseline length range. As shown in Appendix B for a simplified case,




Figure 6. Debiasing function, $\beta^{-1}(|u|)$, derived from comparison of the estimated variances generated from simulated data sets associated with 90 GRMHD simulations to the visibility amplitude power spectra resulting from the GRMHD movie directly. Below $|u| < 2 \text{ G}\lambda$, the LMT calibration procedure precludes accurate variance estimates. Above $9 \text{ G}\lambda$, there are no data. The region from 6 to $7.5 \text{ G}\lambda$ has poor (u, v) -coverage, resulting in significant underestimates of the variance.

these kinds of correlations produce heavily biased variance estimates in which only one or two baselines contribute, typically dramatically underestimating the bias in the relevant baseline length bins, as seen in the examples shown.

In contrast, note that between 7.5 and $9 \text{ G}\lambda$ there are five separate baselines, four of which are “following baseline pairs”—LMT-SPT/SMA-SPT and SMT-SPT/PV-SPT—in which the two baselines traverse the same region in the (u, v) -plane but at times separated by hours (Paper IV). Thus, within this baseline range, there are more statistically independent samples than implied by the number of apparent baselines, and many more than between 6 and $7.5 \text{ G}\lambda$. Correspondingly, the accuracy of the variance estimates improves dramatically beyond $7.5 \text{ G}\lambda$.

The magnitude of the bias, β , depends on the temporal power spectrum of the fluctuation spectra and thus is entangled with the statistical property we wish to measure. In principle, we could construct an a priori debiasing function, $\beta^{-1}(|u|)$, for a given set of observations as a function of baseline length and temporal power spectrum of the putative fluctuations. In practice, it is simpler to utilize the libraries of simulated data to effectively “measure” the debiasing factor for specific classes of models that share similar temporal properties. We present such an empirical calibration here for the `iNoisy` and GRMHD models, of which the latter is expected to be more physically relevant and utilized in Papers IV and V.

The procedure to estimate the debiasing functions is straightforward:

1. Generate an ensemble of simulated observations matching the 2017 EHT Sgr A* campaign.
2. Estimate the variance as described in Sections 4.1–4.3.
3. Construct the anticipated power spectrum, \hat{P}_s , from the “truth” movie as described in Section 2 on each day.
4. Generate an estimated debiasing factor for each baseline length bin by minimizing the joint χ^2 among all models,

observation days, and the estimates of the variance and its error:

$$\chi^2(\beta_s^{-1}) = \sum_{\text{ens. day}} \sum_s \frac{[\log(\beta_s^{-1} \sigma_s^2) - \log(\hat{P}_s)]^2}{(\text{err}_s / \sigma_s^2)^2}. \quad (9)$$

We generate an estimate of the debiasing function using the 90 simulations employed in the M/D calibration in Paper IV. This set of mock observations is generated from GRMHD simulations appropriate for Sgr A*, each of which is composed of simulated visibility data for both bands and all days of the reported 2017 Sgr A* EHT campaign. This is shown in Figure 6 and follows the pattern anticipated by the sparsity of the baselines: baseline lengths with few/many baselines contributing have large/small corrections.

The debiased variance estimates for the three GRMHD examples shown in Figure 5 are presented in Figure 7. These three simulations are taken from the 10 simulations used to validate the M/D calibration and are therefore distinct from those within the ensemble used to estimate the debiasing function. They show excellent agreement with the fluctuation power spectrum obtained directly from the simulated images.

4.6. General Application: Limiting Assumptions and Potential Extensions

While we demonstrate and validate the data-driven variability characterization presented in this section using the 2017 EHT Sgr A* campaign, the technique is more widely applicable, albeit subject to some nominal limitations.

First, this method relies on a sufficient density and resampling of visibilities within the (u, v) -plane exists. In the absence of more than three points per patch, it is not possible to reconstruct the detrended excess variance. In the absence of many such patches, the resulting estimates are highly uncertain.

Second, the debiasing procedure outlined in Section 4.2 only results in accurate estimates of the excess variance and its uncertainty when the former exceeds the variation due to the intrinsic thermal uncertainty.

Third, the method does not account for correlations that may be present among different regions in the (u, v) -plane. While not a formal limitation on the method’s application, it nevertheless limits the interpretation of the reconstructed variances.

This method also makes a handful of specific choices that may be relaxed. The assumption of azimuthal symmetry, which was exploited to improve the precision of the variance estimates, may be removed when the (u, v) -coverage is sufficiently complete. The debiasing function presented in Section 4.5 was constructed for a specific set of observations and anticipated mock image ensemble. An analogous debiasing function could be separately reconstructed for a different application, given an appropriate set of observations and mock images from which to derive it.

Finally, the interpretation of the reconstructed variances depends on the nature of the structural variability. Where it is well described by a set of stochastic fluctuations about a mean image, the measured variability may directly be interpreted as constraining the power spectrum of the fluctuations. Where the variability is associated with coherent motions, the interpretation is more complicated.




Figure 7. Debiased data-driven estimates of the variance for simulated data sets generated using the 2017 EHT Sgr A* campaign parameters assuming three different GRMHD simulations from the validation set used in Paper IV. Gray triangles show an estimate of the thermal noise in each radial baseline bin. The time- and azimuthally averaged visibility variances associated with the idealized visibility functions of the input movies are shown for each of the four observation days by the red lines. The orange shaded region indicates the 95% confidence level region spanned by the broken power-law fit to the variance between 2.5 and 6 Gλ described in Section 4.3.3.

5. Bayesian Noise Reconstruction

Implicit in the noise estimates obtained in Section 4 is a model for the source structure and its variability that results in smoothly varying visibility amplitudes and noise that is stationary across the multiple observation days. No model for the station gains is assumed, and no effort to utilize the phase information is made. However, it is possible to simultaneously reconstruct the average source structure and the additional noise associated with the variability within standard maximum likelihood analysis schemes.

For Gaussian likelihoods, i.e., assuming Gaussian errors (as is appropriate when fitting complex visibilities), the log-likelihood is

$$\mathcal{L} = -\frac{1}{2} \mathbf{y}^\dagger \mathbf{C}^{-1} \mathbf{y} - \frac{1}{2} \log(\|\mathbf{C}\|), \quad (10)$$

where $y_j = V_j - \hat{V}(u_j, v_j)$ is the difference between the observed and model complex visibilities and \mathbf{C} is the covariance. This differs from the usual quadratic expression by the inclusion of the logarithmic normalization term, which will be critical in what follows.

The essence of Bayesian noise reconstruction is that, in addition to the $\hat{V}(u, v)$, the data covariance \mathbf{C} is also replaced by some parameterized model whose parameters are jointly optimized with those from the visibility model. In this strategy, the logarithmic normalization is critical, as it penalizes excess noise. That is, the optimal joint source and noise model is one that has just enough noise to properly normalize the log-likelihood, but no more.¹⁵⁴

As described in Section 3, in what follows we will assume that \mathbf{C} is diagonal, subject to the assumptions and limitations described there. In this case the normalization term reduces to

$$\log(\|\mathbf{C}\|) = \sum_j \log(\sigma_j^2), \quad (11)$$

where σ_j^2 is the j th diagonal element of \mathbf{C} , corresponding to the effective uncertainty associated with the j th complex visibility.

¹⁵⁴ It is straightforward to show that when $\mathbf{C} = \sigma^2 \mathbf{1}$, where $\mathbf{1}$ is the identity and the single parameter is σ , the optimal noise model (value of σ) is that for which the standard reduced- χ^2 is unity.




Figure 8. Joint posteriors on the normalized intensity and FWHM of a Gaussian fitted without any noise modeling to simulated data sets in which no additional noise was added (black), additional σ_{sys} and σ_{ref} were added as Gaussian random variables (green), and additional σ_{sys} , σ_{ref} , and σ_{var} are added as Gaussian random variables (blue). The impact of the unmodeled or misspecified noise is to substantially bias the reconstructed parameter estimates (i.e., by many σ). Filled contours correspond to the 50%, 90%, and 99% quantiles. The truth values used to generate the simulated data are shown in red.

5.1. Implementation of Uncertainty Modeling

Multiple specific realizations of the noise modeling procedure outlined above have been implemented in the THEMIS analysis framework (Broderick et al. 2020a). In each case, the “noise” model, or uncertainty model, is characterized by a parameterized function that is added in quadrature to the existing uncertainties on the complex visibilities. That is, for the j th complex visibility we set its effective uncertainty by

$$\sigma_j^2 = \sigma_{\text{th},j}^2 + \sigma^2(u_j, v_j; \mathbf{q}), \quad (12)$$

where $\sigma_{\text{th},j}^2$ is the reported thermal error and $\sigma^2(u_j, v_j; \mathbf{q})$ is the additional component evaluated for some set of




Figure 9. Joint posteriors on the normalized intensity, FWHM, and relevant noise model parameters when a Gaussian with the appropriate noise model is fit to simulated data sets in which additional σ_{sys} and σ_{ref} were added as Gaussian random variables (green), and additional σ_{sys} , σ_{ref} , and σ_{var} are added as Gaussian random variables (blue). Filled contours correspond to the 50%, 90%, and 99% quantiles. Panels showing the joint posteriors among the noise model parameters are shaded light red. The truth values used to generate the simulated data are shown in red.

parameters q . These differ in the particular form of $\sigma^2(u_j, v_j; \mathbf{q})$. The most general uncertainty model employed is constructed from three subcomponents.

The first is a systematic term associated with the residual nonclosing errors that is proportional to the visibility amplitudes:

$$\sigma_{\text{sys}}^2(u_j, v_j; f) = f^2 |V_j|^2, \quad (13)$$

where anticipated values of f are of order 1% (Paper II).

The second is a refractive scattering term that accounts for the long-baseline fluctuations resulting from the refractive scintillation toward the Galactic center (see, e.g., Johnson et al. 2018; Issaoun et al. 2021). Predictions for the amplitudes of the fluctuations due to refractive scattering are typically only weakly dependent on baseline length beyond $|u| \approx 1 \text{ G}\lambda$ (Paper III). Therefore, we incorporate a term that imposes a

uniform ((u, v) -independent) floor:

$$\sigma_{\text{ref}}^2(u_j, v_j; \sigma_T) = \sigma_T^2, \quad (14)$$

where typical values of σ_T can be as high as 0.4%. This term only ever contributes significantly at longer baselines when the former two terms have fallen below σ_{ref}^2 .

Finally, the third is a contribution that accounts for the structural variability,

$$\sigma_{\text{var}}^2(u_j, v_j; a, b, c, u_0) = n(\sqrt{u_j^2 + v_j^2}), \quad (15)$$

where $n(|u|)$ is defined in Equation (7). While this specific functional form is motivated by GRMHD simulations (see Section 2), it is sufficiently flexible to encompass a wide variety of potential structural variability.




Figure 10. Lower left: joint posteriors on the normalized intensity, ring diameter, model amplitudes and phases, and smoothing scale for an mG-ring model (see Paper IV for detailed definition), and relevant noise model parameters when a Gaussian with the appropriate noise model is fit to simulated data sets in which additional σ_{sys} , σ_{ref} , and σ_{var} are added as Gaussian random variables (blue). Filled contours correspond to the 50%, 90%, and 99% quantiles. Panels showing the joint posteriors among the noise model parameters are shaded light red. The truth values used to generate the simulated data are shown in red. Top right: a summary of the absolute residuals of the reconstructed structural parameters, after marginalization over all other parameters and normalized by the one-dimensional posterior standard deviation for a variety of mG-ring analyses. Shown are analyses of simulated data sets produced with no additional noise (black circles), with σ_{sys} and σ_{ref} added as Gaussian random variables (green squares), and σ_{sys} , σ_{ref} , and σ_{var} added as Gaussian random variables (blue diamonds). Filled and open points show the results of analyses with and without including the relevant noise model, respectively. For reference, 1σ , 2σ , and 3σ lines are shown in red.

The combined uncertainty model is then

$$\sigma^2(u_j, v_j; f, \sigma_T, a, b, c, u_0) = \sigma_{\text{sys}}^2 + \sigma_{\text{ref}}^2 + \sigma_{\text{var}}^2, \quad (16)$$

of which some or all parameters can be fixed, which will be useful to model only a subset of the model components. This is then inserted into Equation (12) to obtain the uncertainties on the real and imaginary components of complex visibilities.

5.2. Validation

We report three sets of validation experiments of the Bayesian noise modeling implemented in THEMIS. These correspond to the different validation levels described in

Section 3.3. In each, we demonstrate that the average source structure and noise power spectrum can be faithfully recovered.

All of the analyses presented here are performed as the THEMIS-based analogs described in Papers III and IV. Specifically, they make use of the scan-averaged, complex visibilities, and the LMT and JCMT pre-processing calibration steps described in Section 4.1 are applied. The complex station gains are reconstructed simultaneously with the image reconstruction.

5.2.1. Gaussian Noise Reconstructions

We begin with simulated data sets produced from a simple source structure and independent Gaussian fluctuations added directly to the visibilities. Note that in this set of tests there are




Figure 11. Reconstructed images (top) and noise (bottom) for the crescent (left), point (middle), and elliptical disk (right) `iNoisy` simulated data sets. In each, on the top line the time-averaged truth image (left), maximum-likelihood (middle), and posterior-average (right) images are shown, with nine additional random draws from the posterior shown below. To recover physical brightness units, all images have been renormalized by a common factor so that the total flux of the mean image matches to 2.5 Jy. In the bottom panels, the data-driven nonparametric estimates from Section 4 are shown in black, and the allowed noise models permitted by the assumed priors on the noise model parameters are shown in blue. Finally, the reconstructed posterior of the noise is shown in orange.

no guarantees that the associated image is positive definite. However, the manner in which additional noise has been added to the data matches exactly that being modeled.

Simulated data sets are produced with the baseline coverage and uncertainties similar to the 2017 April 7 EHT observations of Sgr A* for a Gaussian brightness map with a total flux of 1 Jy and an FWHM = 50 μ as. Various assumptions are made about the inclusion of additional fluctuations, which are independently generated for the systematic, refractive, and variability components. We consider three cases here:

1. *No additional noise is added:* In this case, the true values of the relevant parameters are $f=0$, $\sigma_T=0$, $\sigma_{\text{var}}=0$.
2. *Only systematic and refractive noise is added:* In this case, the true values of the relevant parameters are $f=1\%$, $\sigma_T=0.7\%$, and $\sigma_{\text{var}}=0$.
3. *The full noise model is added:* In this case, the true values of the relevant parameters are $f=1\%$, $\sigma_T=0.7\%$, $a=5\%$, $u_0=2\text{ GA}$, $b=3$, and $c=2$.

These are then fit with a Gaussian brightness map model, with and without employing the relevant model for the additional noise.

Figure 8 clearly indicates the consequences for failing to account for the additional fluctuations on the underlying data.

When no additional noise is included, the posteriors on the total flux and the FWHM faithfully recover the true values. However, when additional sources of noise are included but are unmodeled, large biases are induced, i.e., many σ deviations from the truth. It is mitigating precisely these biases that is the focus of this paper and critical to Papers III and IV.

In contrast, the joint posteriors when the model being fit includes the appropriate noise model are shown in Figure 9. In this case, the parameters of the image structure are faithfully recovered, albeit with an appropriate inflation of the uncertainty. In addition, the parameters of the underlying noise parameters are faithfully recovered as well.

A similar experiment is performed for a more complicated source model that provides good fits to the source structure in the 2017 EHT Sgr A* data (Paper IV), specifically, the “m-ring” construction from Johnson et al. (2020), in which the truth image is a narrow ring with an azimuthal flux distribution decomposed into a truncated Fourier series and then convolved with a circular Gaussian. The model parameters are the total flux, I , ring radius, R , Fourier mode amplitudes and phases, $\{A_m, \phi_m\}$, and FWHM of the Gaussian smoothing kernel (for detailed model specification see Section 4 of Paper IV, though note that we do not include the additional Gaussian component employed there for this test). For this test, we truncate the




Figure 12. Images (top) and noise posteriors (bottom) from mG-ring fits to synthetic data sets on multiple days (2017 April 6 and 7 EHT Sgr A* low-band (u, v -coverage) generated from three GRMHD simulations. In each, on the top line the time-averaged truth image (left), maximum-likelihood (middle), and posterior-average (right) images are shown, with nine additional random draws from the posterior shown below. To recover physical brightness units, all images have been renormalized by a common factor so that the total flux of the mean image matches to 2.5 Jy. In the bottom panels, the data-driven nonparametric estimates from Section 4 are shown in black, and the allowed noise models permitted by the assumed priors on the noise model parameters are shown in blue. Finally, the reconstructed posterior of the noise is shown in green.

Fourier series at $m = 2$. Data are generated in a similar fashion to that for the Gaussian test and analyzed with and without the Bayesian noise modeling.

The top right panel of Figure 10 indicates the necessity of including the Bayesian noise reconstruction: when the excess noise is not modeled (open points), the structural parameters are biased by nearly 100σ in some cases; in contrast, including the noise modeling yields quantitatively accurate parameter estimates. Joint posteriors for the data set in which all additional sources of noise are added are shown in Figure 10. As with the simpler Gaussian image structure, the Bayesian noise reconstruction permits an accurate simultaneous recovery of the structural and noise parameters. This improvement is in part associated with the inflation of the parameter posterior widths resulting from the inclusion of additional contributions to the uncertainties of the individual complex visibilities.

We conclude that Bayesian noise reconstruction satisfactorily mitigates the presence of additional variability when directly applied to the complex visibilities.

5.2.2. *iNoisy* Reconstructions

The *iNoisy* data sets used to validate the image reconstructions in Paper III and described at the beginning of

Section 4.4.1 provide a natural set of validation tests. Despite the artificial nature of the simulated images, there are some salient differences with tests in the preceding subsection. First, the images are more complex, and we apply a more complicated source model—an adaptive bicubic raster model appropriate for image reconstruction (see Broderick et al. 2020b; Paper III)—with an associated increase in model complexity. Second, because fluctuations are applied directly to the image, significant correlations are induced among the complex visibilities. Third, the underlying noise spectrum is not known a priori, and therefore the specific quantitative reconstructions of the noise parameters cannot be compared to some truth in the form shown in Figure 9. Thus, we compare to the data-driven nonparametric estimates from Section 3.

Simultaneous image and noise reconstructions are shown in Figure 11 for three examples of the *iNoisy* simulated data sets. The morphology of the reconstructed images faithfully matches that of the mean images in the underlying truth. A gross sense of the breadth of the posterior is indicated by the samples shown.

The normalized variance in both instances is shown in the bottom panels of Figure 11. The data-driven, nonparametric estimates serve two purposes in these analyses. First, they




Figure 13. Reconstructed images (top) and noise posteriors (bottom) for synthetic data sets on multiple days (2017 April 6 and 7 EHT Sgr A* combined high- and low-band (u, v) -coverage) generated from three GRMHD simulations. In each, on the top line the time-averaged truth image (left), maximum-likelihood (middle), and posterior-average (right) images are shown, with nine additional random draws from the posterior shown below. To recover physical brightness units, all images have been renormalized by a common factor so that the total flux of the mean image matches to 2.5 Jy. In the bottom panels, the data-driven nonparametric estimates from Section 4 are shown in black, and the allowed noise models permitted by the assumed priors on the noise model parameters are shown in blue. The reconstructed posterior of the noise is shown in orange. For comparison, the posterior of the noise from the mG-ring fits in Figure 12 is reproduced in green.

inform the priors on the noise model, which employ the data-driven amplitude at $|u| = 4 \text{ G}\lambda$ and the long-baseline power-law index b . However, these are weakly informative, predominantly setting a lower bound on the noise. The range of normalized variances associated with the permitted noise models is reflected by the blue shaded regions. To prevent overinterpretation of the simulated data, we intentionally impose strong lower limits on the noise via these priors; only very weak, noninformative upper limits are enforced.

Second, the data-driven, nonparametric estimates provide a comparison by which to assess the posteriors on the parameters of the noise models, shown by the orange shaded regions in Figure 11. These posteriors are well matched to the data-driven estimates within and beyond the range for which the latter are well constrained. Note that the assumed priors include many values of the noise parameters for which this is not the case, especially parameters that exhibit large degrees of excess noise that are strongly disfavored.

5.2.3. GRMHD Simulation Reconstructions

Finally, we turn to GRMHD simulations, which exhibit physically motivated stochastic and coherent substructures in the simulated images. The simulated GRMHD data sets

described in Section 4.4.2 for the April 6 and 7 (u, v) -coverage of the 2017 EHT Sgr A* campaign are used.

We perform two sets of validation experiments with the GRMHD simulation data sets, distinguished by the image model employed. In both sets of experiments we employ the same procedure to set the priors on the noise model using the data-driven, nonparametric estimates as that employed during the *iNoisy* tests. These priors are reflected in the blue shaded regions in Figures 12 and 13.

In the first, we reconstruct the simulated data sets with a parameterized ring model appropriate for comparison with the compact ring structures seen in M87* and Sgr A*: the mG-ring model described in Paper IV and a simple extension of the m-ring model introduced in Section 5.2.1, differing only by the addition of a central Gaussian component to probe the magnitude of the central flux depression. This is similar to geometric ring reconstructions of the Sgr A* data in Paper IV.

Unlike the test in Section 5.2.1, we do not have an unambiguous set of mG-ring-parameter truth values to validate against, and thus we limit ourselves to general image comparisons. Figure 12 shows mG-ring reconstruction image posteriors in comparison to the average truth images for the same three GRMHD examples shown in Sections 4.4.2 and 4.5. The general size and brightness distributions of the mG-ring images

are similar to those of the underlying average truth, blurred to the ostensible resolution of $15 \mu\text{as}$, limited by the restricted freedom of the mG-ring model to produce radially asymmetric brightness profiles. In all cases, the reconstructed noise posteriors match those estimated by the data-driven nonparametric estimates. Specifically, the amplitudes near $4 \text{ G}\lambda$ and the power-law index between 2.5 and $6 \text{ G}\lambda$ are well reproduced.

The second validation experiment mirrors that of the *iNoisy* demonstration: we utilize an adaptive bicubic raster model appropriate for image reconstruction (Broderick et al. 2020b). This directly supports the Sgr A* image reconstructions presented in Paper III and is a procedure similar to that employed by the THEMIS reconstructions presented therein. The results for the same three GRMHD simulation data sets are shown in Figure 13. As found in the *iNoisy* case, the morphology of the reconstructed image faithfully matches that in the average truth after convolving both with $15 \mu\text{as}$ beams. The reconstructed noise estimate posteriors, shown by the orange bands, are again consistent with those from the data-driven nonparametric estimates. In particular, the amplitude at $4 \text{ G}\lambda$ and the long-baseline power-law index of the excess normalized variance are faithfully recovered.

The success found in both sets of experiments is notable given the much larger degree (by 1–2 orders of magnitude) of additional noise present than the previous *iNoisy* experiments. More importantly, the noise estimates from both experiments are also consistent with each other, indicating robustness to variations in the underlying image model specification.

5.3. General Application: Limiting Assumptions and Potential Extensions

We have made a number of specific choices regarding the form and properties of the noise models, with the goal of applying the noise modeling technique to horizon-resolving black hole imaging analyses. However, there are many other potential natural applications—e.g., the characterization of variability in microquasars and subparsec radio emission from astrophysical jets—that may be incorporated with a handful of minor extensions.

The assumed broken power-law form of the noise model in Equation (7), while well justified for GRMHD accretion simulations and reasonably generic, may not apply in general. However, there is no obstacle to implementing alternative functional forms for the noise. Such alternatives could, e.g., relax the assumption of azimuthal symmetry by including a parameterized azimuthal structure. Similarly, the assumption of no nonzero off-diagonal terms in the covariance—which may be generated, e.g., by coherent variations in the image structure—may also be relaxed. Such would require a model for the particular structure of the anticipated off-diagonal terms.

An important limitation of the procedure as presented is the lack of any model for temporal correlations. Again, this limitation might be relaxed at the expense of specifying an appropriate model. However, in the absence of such an extension to the model, we retain a requirement on the data: a sufficient number of statistically independent samples of the complex visibility function must be present at all locations in the (u, v) -plane. For Sgr A*, this requirement precludes single-day analyses, for which subhour temporal correlations can bias the noise model reconstructions significantly in the absence of additional source realizations. Combining at least 2 days, and thereby better conditioning the data to the underlying




Figure 14. Estimates of the mean (top) and variance (bottom) for the M87* sampled with $\Delta u = 1 \text{ G}\lambda$. In both cases, the data have been normalized by the intrasite baselines and the LMT gains have been approximately calibrated assuming that the LMT-SMT baselines lie on a Gaussian with FWHM $60 \mu\text{as}$. To avoid large phase decoherences, we have further phase-calibrated JCMT. For reference, the range of visibility amplitudes from the crescent component of the xs-ringauss fit presented in Figure 5 of M87* Paper IV is shown by the shaded red region in the top panel. Variance estimates for $|u| < 2.5 \text{ G}\lambda$ are excluded owing to the LMT calibration procedure.

assumption of the model, is sufficient to mitigate these biases in the applications to the 2017 EHT Sgr A* campaign.

As with the data-driven variance estimation, the interpretation of Bayesian noise modeling depends on the origin of the underlying variability. Where it is due to stochastic fluctuations about a mean, the reconstructed noise model is again a direct measurement of the spatial power spectrum. Where coherent secular motions dominate the variability, the interpretation is more complicated. This ambiguity is similar to that surrounding the meaning of the reconstructed mean image.

6. Application to M87*

As a first science demonstration we apply the data-driven variability characterization and Bayesian noise reconstruction to the 2017 EHT observations of M87*. The estimated gravitational timescale of M87* is 9 hr, and thus little intraday variability is expected, with the possibility of interday variability across the 7 days of the 2017 EHT M87* campaign (M87* Paper II, Satpathy et al. 2022). This expectation is supported by the image and model reconstructions of M87*, which show no significant variation from April 5 to 6 and from April 10 to 11 and modest variations between the two pairs of observing days (M87* Paper IV; M87* Paper VI).

The analyses presented here differ from those in M87* Papers I–VI in two important respects. First, we analyze the entire data set simultaneously, combining the information across multiple observation nights. Second, we explicitly disregard the overall compact flux via the light-curve normalization procedure described in Section 4.1. Because M87* does contain significant extended structure, which is presumably




Figure 15. Reconstructed images (top) and noise posteriors (bottom) for the EHT observations of M87* on a single day (2017 April 10; left) and combined across all days (2017 April 5, 6, 10, and 11; right). The top row shows maximum likelihood (left), posterior average (middle), and standard deviation (right) images, with nine additional random draws from the posterior shown below. To recover physical brightness units, all images have been renormalized by a common factor so that the total flux of the mean image matches the mean of the light curve. In the bottom panels, the reconstructed noise posterior (orange) is shown in comparison to the allowed noise models permitted by the assumed priors (blue, covering the entire range) and typical thermal noise estimates (gray triangles). For reference, the data-driven nonparametric variance estimates from Figure 14, constructed from the full 2017 EHT M87* campaign, are reproduced (black points).

static across the entire observing campaign, we estimate the light curve associated with the compact structure via the intrasite baselines, i.e., SMA-JCMT and ALMA-APEX, using the variance weighted mean for scans in which more than one intrasite visibility amplitude is available.

6.1. Data-driven Variability Estimate

We begin with the application of the data-driven, model-agnostic characterization of the variability as a function of baseline length described in Section 4. The empirically derived mean visibility amplitudes and their variance across all 4 days




Figure 16. Joint posteriors on the noise model parameters from the analysis of the 2017 EHT observations of M87*. Cases shown are when only the 2017 April 10 data set is analyzed (red, upper right triangle) and when all days are analyzed (blue, lower left triangle). Contours indicate the 50%, 90%, and 99% quantiles.

are shown in Figure 14. The mean amplitudes exhibit the clear double-humped structure consistent with a narrow crescent, already apparent in the amplitudes themselves (M87* Paper III). The normalized amplitude variances are generally small, consistent with the typical thermal errors (though still much larger than the systematic uncertainty). That is, as anticipated, there is little evidence for stochastic variability in M87* from this model-agnostic, data-driven approach. We now move on to Bayesian source and noise reconstructions.

6.2. Bayesian Noise Reconstructions

The expected absence of intraday variability precludes placing strong priors on the noise model. Thus, we do not apply priors based on the data-driven variance estimates from

the preceding section, and instead we assume linear priors in the ranges $\sigma_T \in [0, 0.02]$, $f \in [0, 0.1]$, $a \in [0, 0.5]$, $u_0 \in [1 \text{ G}\lambda, 10 \text{ G}\lambda]$, $b \in [0.5, 6]$, and $c \in [0.5, 6]$. The range of noise covers is indicated by the blue shaded areas in Figure 15 and covers the entirety of the plot region.

The absence of intraday variability is borne out by the Bayesian noise reconstruction on a single day. The left panels of Figure 15 show draws from the posterior of the reconstructed image of the EHT observations of M87* on 2017 April 10. This day has the fewest scans of any of the observations of M87* during the 2017 EHT campaign and is correspondingly more uncertain, a fact that is reflected in the variety of potential images in the imaging posterior (Figure 15, middle left panels).

In addition to image reconstruction, we simultaneously fit the noise model to the data and find no evidence for any excess

noise. The bottom left panel of Figure 15 shows that the posterior distribution of the required additional noise on 2017 April 10, indicated by the orange band, is generally small in comparison to both the thermal errors and the data-driven, model-agnostic estimates from all four observing days presented in Figure 14.

While there is little evidence for intraday variability, interday variability is obviously present in the image reconstructions in M87* Paper IV and M87* Paper VI. This conclusion is borne out by the multiday image reconstructions shown in the right panels of Figure 15. In stark contrast to the single-day analysis, when multiple observation days are combined, there is a clear need for additional noise, the posterior range of which is shown by the orange band in the bottom right panel, even though marginally subthermal. Above $4\text{ G}\lambda$, i.e., on characteristic scales smaller than $50\ \mu\text{as}$, the required additional noise matches that anticipated by the data-driven, model-agnostic analysis.

A quantitative comparison of the required additional variability obtained from the Bayesian noise modeling is presented in Figure 16. Consistent with the lack of significant Galactic scattering toward M87*, no substantial σ_T is required. Estimates of the additional systematic noise from the statistics of closure quantities are consistent with the roughly 1% values obtained (M87* Paper III). On a single day, no additional variability noise is required, i.e., $a < 0.05\%$ at 2σ . Across all observation days, $a = 1.00\% \pm 0.25\% \pm 0.45\%$ at 1σ and 2σ , respectively. No other parameters of the noise model are meaningfully constrained in this example application.

7. Summary and Conclusions

Intraday variability presents a novel challenge for high-frequency VLBI observations, like those performed by the EHT. Traditional image reconstruction algorithms are predicated on static source structures that permit the combination of VLBI observations throughout the observing night, i.e., Earth aperture synthesis, an assumption explicitly violated by variable targets. At the same time, the nature and properties of the source variability are of intrinsic interest, informing the underlying physical properties of the source (Georgiev et al. 2022).

For the sources of greatest interest to the EHT, Sgr A* and M87*, this variability is associated with stochastic fluctuations driven by MHD turbulence. Thus, we have developed methods to reconstruct the mean source structure and statistically characterize the variability around it. By doing so, we reap the benefits underlying Earth aperture synthesis—better (u, v) -coverage and larger effective data sets, both of which increase the fidelity and volume of information that may be extracted—while addressing the variable nature of the source. These methods are more broadly applicable to any time-variable source, though they are most naturally applied to the imaging and/or modeling of sources exhibiting stochastic variations.

In GRMHD simulations, the strongest structural variability occurs on the longest timescales and largest spatial scales, i.e., the spatiotemporal power spectrum is “red–red.” Therefore, Georgiev et al. (2022) find that it is possible to substantially reduce the degree of variability that must be mitigated by utilizing light-curve-normalized visibility data. For GRMHD simulations of Sgr A* and M87*, the remaining power spectrum is well described by a broken power law that typically peaks below $2\text{ G}\lambda$.

We have presented a data-driven nonparametric method for directly estimating the power spectrum of source image fluctuations from multiday sets of observations, like those by the EHT. For the 2017 EHT Sgr A* observing campaign, we have calibrated the resulting power spectrum estimates against GRMHD simulations. In particular, we have demonstrated the ability to faithfully extract the magnitude and long-baseline power-law index of the image fluctuation power spectrum near $4\text{ G}\lambda$, corresponding to scales of $50\ \mu\text{as}$. Results of applying this procedure to Sgr A* are contained in Paper IV, and the implications of the measured a and b noise model parameters for GRMHD models of Sgr A* are discussed in Paper V. These estimates of the Sgr A* variability are explicitly used to inform priors on the noise modeling employed by the THEMIS mG-ring analyses in Paper IV and the THEMIS image reconstructions in Paper III; the remaining imaging methods employed in Paper III survey over ranges of noise model parameters informed by these analyses.

We further present a formalism, Bayesian noise reconstruction, by which the statistical properties of the variability are constrained simultaneously with the mean source structure. These make use of parameterized “noise models,” in which an excess uncertainty budget is included within a self-consistent likelihood. In applying this procedure, we necessarily focus exclusively on the diagonal of the visibility covariance, ignoring correlations between the visibilities at different locations in the (u, v) -plane. This procedure has been implemented in the THEMIS parameter estimation framework (Broderick et al. 2020a) and validated with a number of mock data sets.

We conclude that the Bayesian noise reconstruction scheme is effective at mitigating the impact of even substantial variability on the problem of source reconstruction and provides self-consistent estimates of the intrinsic variability. We have tested the Bayesian noise reconstruction algorithm on simulated data tests that span a wide range of mean images and types of variability, extending to the simultaneous reconstruction of mean images and power spectra from GRMHD movies. In all cases, we are able to faithfully recover both the image structure and excess variability noise. These reconstructions are robust in the sense that any model possessing a sufficient number of degrees of freedom recovers similar images and similar “noise” power spectra. Results of a variety of imaging and modeling analyses of the EHT Sgr A* observations are presented in Papers III and IV. As with the data-driven variability characterization, the recovered noise model from the Bayesian noise reconstruction directly informs models of variability within the emission region.

We have applied both methods to M87*, for which $GM/c^3 = 9\text{ hr}$. Image reconstructions of the EHT M87* data do not show significant variation among neighboring days, implying little intraday variability. We confirm this conclusion by analyzing the 2017 April 10 observation, finding no evidence for variability. Combining all four observing days, 2017 April 5, 6, 10, and 11, we recover the interday variability observed across the week. In particular, we find excellent agreement between the data-driven nonparametric estimates and the self-consistently obtained modeled variability noise. Moreover, the nonvariability components in the noise model, i.e., refractive scattering and fractional systematic error components, return their anticipated values for M87*: negligible and 1%, respectively.

Both of the methods presented here have potential applications well beyond EHT data sets. As demonstrated with M87*, they provide a natural method for estimating the degree of variability for sources that vary across multiple observation epochs. Moreover, by simultaneously recovering the variability and the mean flux distribution, Bayesian noise reconstruction enables the self-consistent combination of the data from multiple observations. That is, by construction, Bayesian noise modeling permits self-consistent, data-driven averaging across multiple observations, with the potential to result in more accurate mean image estimates.

A number of the assumptions made here regarding the particular form of the noise model are informed by our ultimate application to EHT analyses of Sgr A* and may be relaxed. Chief among these are azimuthal symmetry and the assumed vanishing of the off-diagonal elements of the covariance. The development of an appropriate noise model is source dependent. Nevertheless, it is clear that in addition to enabling traditional VLBI analysis techniques, the ability to detect and characterize variability opens a new window onto the dynamical processes at work in VLBI targets.

The Event Horizon Telescope Collaboration thanks the following organizations and programs:

The Academia Sinica; the Academy of Finland (projects 274477, 284495, 312496, 315721); the Agencia Nacional de Investigación y Desarrollo (ANID), Chile via NCN19_058 (TITANs) and Fondecyt 1221421, the Alexandervon Humboldt Stiftung; an Alfred P. Sloan Research Fellowship; Allegro, the European ALMA Regional Centre node in the Netherlands, the NL astronomy research network NOVA and the astronomy institutes of the University of Amsterdam, Leiden University and Radboud University; the ALMA North America Development Fund; the Black Hole Initiative, which is funded by grants from the John Templeton Foundation and the Gordon and Betty Moore Foundation (although the opinions expressed in this work are those of the author(s) and do not necessarily reflect the views of these Foundations); Chandra DD7-18089X and TM6-17006X; the China Scholarship Council; China Postdoctoral Science Foundation fellowship (2020M671266); Consejo Nacional de Ciencia y Tecnología (CONACYT, Mexico, projects U0004-246083, U0004-259839, F0003-272050, M0037-279006, F0003-281692, 104497, 275201, 263356); the Consejería de Economía, Conocimiento, Empresas y Universidad of the Junta de Andalucía (grant P18-FR-1769), the Consejo Superior de Investigaciones Científicas (grant 2019AEP112); the Delaney Family via the Delaney Family John A. Wheeler Chair at Perimeter Institute; Dirección General de Asuntos del Personal Académico-Universidad Nacional Autónoma de México (DGAPA-UNAM, projects IN112417 and IN112820); the Dutch Organization for Scientific Research (NWO) VICI award (grant 639.043.513) and grant OCENW.KLEIN.113; the Dutch National Supercomputers, Cartesius and Snellius (NWO Grant 2021.013); the EACOA Fellowship awarded by the East Asia Core Observatories Association, which consists of the Academia Sinica Institute of Astronomy and Astrophysics, the National Astronomical Observatory of Japan, Center for Astronomical Mega-Science, Chinese Academy of Sciences, and the Korea Astronomy and Space Science Institute; the European Research Council (ERC) Synergy Grant “BlackHoleCam: Imaging the Event Horizon of Black Holes” (grant 610058); the European

Union Horizon 2020 research and innovation programme under grant agreements RadioNet (No 730562) and M2FINDERS (No 101018682); the Generalitat Valenciana postdoctoral grant APOSTD/2018/177 and GenT Program (project CIDEAGENT/2018/021); MICINN Research Project PID2019-108995GB-C22; the European Research Council for advanced grant “JETSET: Launching, propagation and emission of relativistic jets from binary mergers and across mass scales” (Grant No. 884631); the Institute for Advanced Study; the Istituto Nazionale di Fisica Nucleare (INFN) sezione di Napoli, iniziative specifiche TEONGRAV; the International Max Planck Research School for Astronomy and Astrophysics at the Universities of Bonn and Cologne; DFG research grant “Jet physics on horizon scales and beyond” (Grant No. FR 4069/2-1); Joint Princeton/Flatiron and Joint Columbia/Flatiron Postdoctoral Fellowships, research at the Flatiron Institute is supported by the Simons Foundation; the Japan Ministry of Education, Culture, Sports, Science and Technology (MEXT; grant JPMXP1020200109); the Japanese Government (Monbukagakusho: MEXT) Scholarship; the Japan Society for the Promotion of Science (JSPS) Grant-in-Aid for JSPS Research Fellowship (JP17J08829); the Joint Institute for Computational Fundamental Science, Japan; the Key Research Program of Frontier Sciences, Chinese Academy of Sciences (CAS, grants QYZDJ-SSW-SLH057, QYZDJSSW-SYS008, ZDBS-LY-SLH011); the Leverhulme Trust Early Career Research Fellowship; the Max-Planck-Gesellschaft (MPG); the Max Planck Partner Group of the MPG and the CAS; the MEXT/JSPS KAKENHI (grants 18KK0090, JP21H01137, JP18H03721, JP18K13594, 18K03709, JP19K14761, 18H01245, 25120007); the Malaysian Fundamental Research Grant Scheme (FRGS) FRGS/1/2019/STG02/UM/02/6; the MIT International Science and Technology Initiatives (MISTI) Funds; the Ministry of Science and Technology (MOST) of Taiwan (103-2119-M-001-010-MY2, 105-2112-M-001-025-MY3, 105-2119-M-001-042, 106-2112-M-001-011, 106-2119-M-001-013, 106-2119-M-001-027, 106-2923-M-001-005, 107-2119-M-001-017, 107-2119-M-001-020, 107-2119-M-001-041, 107-2119-M-110-005, 107-2923-M-001-009, 108-2112-M-001-048, 108-2112-M-001-051, 108-2923-M-001-002, 109-2112-M-001-025, 109-2124-M-001-005, 109-2923-M-001-001, 110-2112-M-003-007-MY2, 110-2112-M-001-033, 110-2124-M-001-007, and 110-2923-M-001-001); the Ministry of Education (MoE) of Taiwan Yushan Young Scholar Program; the Physics Division, National Center for Theoretical Sciences of Taiwan; the National Aeronautics and Space Administration (NASA, Fermi Guest Investigator grant 80NSSC20K1567, NASA Astrophysics Theory Program grant 80NSSC20K0527, NASA NuSTAR award 80NSSC20K0645); NASA Hubble Fellowship grant HST-HF2-51431.001-A awarded by the Space Telescope Science Institute, which is operated by the Association of Universities for Research in Astronomy, Inc., for NASA, under contract NAS5-26555; the National Institute of Natural Sciences (NINS) of Japan; the National Key Research and Development Program of China (grant 2016YFA0400704, 2017YFA0402703, 2016YFA0400702); the National Science Foundation (NSF, grants AST-0096454, AST-0352953, AST-0521233, AST-0705062, AST-0905844, AST-0922984, AST-1126433, AST-1140030, DGE-1144085, AST-1207704, AST-1207730, AST-1207752, MRI-1228509, OPP-1248097, AST-1310896, AST-1440254, AST-1555365, AST-1614868, AST-1615796,

AST-1715061, AST-1716327, AST-1716536, OISE-1743747, AST-1816420, AST-1935980, AST-2034306); NSF Astronomy and Astrophysics Postdoctoral Fellowship (AST-1903847); the Natural Science Foundation of China (grants 11650110427, 10625314, 11721303, 11725312, 11873028, 11933007, 11991052, 11991053, 12192220, 12192223); the Natural Sciences and Engineering Research Council of Canada (NSERC, including a Discovery Grant and the NSERC Alexander Graham Bell Canada Graduate Scholarships-Doctoral Program); the National Youth Thousand Talents Program of China; the National Research Foundation of Korea (the Global PhD Fellowship Grant: grants NRF-2015H1A2A1033752, the Korea Research Fellowship Program: NRF-2015H1D3A1066561, Brain Pool Program: 2019H1D3A1A01102564, Basic Research Support Grant 2019R1F1A1059721, 2021R1A6A3A01086420, 2022R1C1C1005255); Netherlands Research School for Astronomy (NOVA) Virtual Institute of Accretion (VIA) postdoctoral fellowships; Onsala Space Observatory (OSO) national infrastructure, for the provisioning of its facilities/observational support (OSO receives funding through the Swedish Research Council under grant 2017-00648); the Perimeter Institute for Theoretical Physics (research at Perimeter Institute is supported by the Government of Canada through the Department of Innovation, Science and Economic Development and by the Province of Ontario through the Ministry of Research, Innovation and Science); the Spanish Ministerio de Ciencia e Innovación (grants PGC2018-098915-B-C21, AYA2016-80889-P, PID2019-108995GB-C21, PID2020-117404GB-C21); the University of Pretoria for financial aid in the provision of the new Cluster Server nodes and SuperMicro (USA) for a SEEDING GRANT approved towards these nodes in 2020; the Shanghai Pilot Program for Basic Research, Chinese Academy of Science, Shanghai Branch (JCYJ-SHFY-2021-013); the State Agency for Research of the Spanish MCIU through the “Center of Excellence Severo Ochoa” award for the Instituto de Astrofísica de Andalucía (SEV-2017-0709); the Spinoza Prize SPI 78-409; the South African Research Chairs Initiative, through the South African Radio Astronomy Observatory (SARAO, grant ID 77948), which is a facility of the National Research Foundation (NRF), an agency of the Department of Science and Innovation (DSI) of South Africa; the Toray Science Foundation; Swedish Research Council (VR); the US Department of Energy (USDOE) through the Los Alamos National Laboratory (operated by Triad National Security, LLC, for the National Nuclear Security Administration of the USDOE (Contract 89233218CNA000001); and the YCAA Prize Postdoctoral Fellowship.

We thank the staff at the participating observatories, correlation centers, and institutions for their enthusiastic support. This paper makes use of the following ALMA data: ADS/JAO.ALMA#2016.1.01154.V. ALMA is a partnership of the European Southern Observatory (ESO; Europe, representing its member states), NSF, and National Institutes of Natural Sciences of Japan, together with National Research Council (Canada), Ministry of Science and Technology (MOST; Taiwan), Academia Sinica Institute of Astronomy and Astrophysics (ASIAA; Taiwan), and Korea Astronomy and Space Science Institute (KASI; Republic of Korea), in cooperation with the Republic of Chile. The Joint ALMA Observatory is operated by ESO, Associated Universities, Inc.

(AUI)/NRAO, and the National Astronomical Observatory of Japan (NAOJ). The NRAO is a facility of the NSF operated under cooperative agreement by AUI. This research used resources of the Oak Ridge Leadership Computing Facility at the Oak Ridge National Laboratory, which is supported by the Office of Science of the U.S. Department of Energy under Contract No. DE-AC05-00OR22725. We also thank the Center for Computational Astrophysics, National Astronomical Observatory of Japan. The computing cluster of Shanghai VLBI correlator supported by the Special Fund for Astronomy from the Ministry of Finance in China is acknowledged.

APEX is a collaboration between the Max-Planck-Institut für Radioastronomie (Germany), ESO, and the Onsala Space Observatory (Sweden). The SMA is a joint project between the SAO and ASIAA and is funded by the Smithsonian Institution and the Academia Sinica. The JCMT is operated by the East Asian Observatory on behalf of the NAOJ, ASIAA, and KASI, as well as the Ministry of Finance of China, Chinese Academy of Sciences, and the National Key Research and Development Program (No. 2017YFA0402700) of China and Natural Science Foundation of China grant 11873028. Additional funding support for the JCMT is provided by the Science and Technologies Facility Council (UK) and participating universities in the UK and Canada. The LMT is a project operated by the Instituto Nacional de Astrófisica, Óptica, y Electrónica (Mexico) and the University of Massachusetts at Amherst (USA). The IRAM 30-m telescope on Pico Veleta, Spain is operated by IRAM and supported by CNRS (Centre National de la Recherche Scientifique, France), MPG (Max-Planck-Gesellschaft, Germany) and IGN (Instituto Geográfico Nacional, Spain). The SMT is operated by the Arizona Radio Observatory, a part of the Steward Observatory of the University of Arizona, with financial support of operations from the State of Arizona and financial support for instrumentation development from the NSF. Support for SPT participation in the EHT is provided by the National Science Foundation through award OPP-1852617 to the University of Chicago. Partial support is also provided by the Kavli Institute of Cosmological Physics at the University of Chicago. The SPT hydrogen maser was provided on loan from the GLT, courtesy of ASIAA.

This work used the Extreme Science and Engineering Discovery Environment (XSEDE), supported by NSF grant ACI-1548562, and CyVerse, supported by NSF grants DBI-0735191, DBI-1265383, and DBI-1743442. XSEDE Stampede2 resource at TACC was allocated through TG-AST170024 and TG-AST080026N. XSEDE JetStream resource at PTI and TACC was allocated through AST170028. This research is part of the Frontera computing project at the Texas Advanced Computing Center through the Frontera Large-Scale Community Partnerships allocation AST20023. Frontera is made possible by National Science Foundation award OAC-1818253. This research was carried out using resources provided by the Open Science Grid, which is supported by the National Science Foundation and the U.S. Department of Energy Office of Science. Additional work used ABACUS2.0, which is part of the eScience center at Southern Denmark University. Simulations were also performed on the SuperMUC cluster at the LRZ in Garching, on the LOEWE cluster in CSC in Frankfurt, on the HazelHen cluster at the HLRS in Stuttgart, and on the Pi2.0 and Siyuan Mark-I at Shanghai Jiao Tong University. The computer resources of the

Finnish IT Center for Science (CSC) and the Finnish Computing Competence Infrastructure (FCCI) project are acknowledged. This research was enabled in part by support provided by Compute Ontario (<http://computeontario.ca>), CalculQuebec (<http://www.calculquebec.ca>) and ComputeCanada (<http://www.computecanada.ca>).

The EHTC has received generous donations of FPGA chips from XilinxInc., under the Xilinx University Program. The EHTC has benefited from technology shared under open-source license by the Collaboration for Astronomy Signal Processing and Electronics Research (CASPER). The EHT project is grateful to T4Science and Microsemi for their assistance with Hydrogen Masers. This research has made use of NASA’s Astrophysics Data System. We gratefully acknowledge the support provided by the extended staff of the ALMA, both from the inception of the ALMA Phasing Project through the observational campaigns of 2017 and 2018. We would like to thank A. Deller and W. Brisken for EHT-specific support with the use of DiFX. We thank Martin Shepherd for the addition of extra features in the Difmap software that were used for the CLEAN imaging results presented in this paper. We acknowledge the significance that Maunakea, where the SMA and JCMT EHT stations are located, has for the indigenous Hawaiian people.

Facility: EHT.

Software: eht-imaging, THEMIS, emcee.

Appendix A

Linear Detrending of Visibility Amplitudes

Given a set of visibility amplitudes, $\{V_j\}$, at positions in the (u, v) -plane of $\{(u_j, v_j)\}$, we produce a linear estimate of the trend, $V(u, v) = \bar{V} + V_u(u - \bar{u}) + V_v(v - \bar{v})$, where (\bar{u}, \bar{v}) may be arbitrary. The three constants, \bar{V} and the gradient (V_u, V_v) , are determined via

$$\begin{pmatrix} \bar{V} \\ V_u \\ V_v \end{pmatrix} = \begin{pmatrix} 1 & S_u & S_v \\ S_u & S_{uu} & S_{uv} \\ S_v & S_{uv} & S_{vv} \end{pmatrix}^{-1} \begin{pmatrix} A \\ B_u \\ B_v \end{pmatrix}, \quad (\text{A1})$$

where

$$\begin{aligned} A &= \sum_j V_j, \\ B_u &= \sum_j V_j(u_j - \bar{u}), \quad B_v = \sum_j V_j(v_j - \bar{v}), \end{aligned} \quad (\text{A2})$$




Figure 17. Example applications of the detrending algorithm to randomly generated data sets with 10 points. We have assumed a complex error of magnitude 0.1 Jy on top of a mean visibility trend with value 1 Jy at (\bar{u}, \bar{v}) and with a gradient in the u direction of $0.5 \text{ Jy } G\lambda^{-1}$. The simulated data are shown in blue. The detrended data are shown in green. The detrended truth is indicated by the dotted line at $v = \bar{v}$, and the range of detrended truth for the range of v in the simulated data set is shown by the band.

and

$$\begin{aligned} S_u &= \sum_j (u_j - \bar{u}), \quad S_v = \sum_j (v_j - \bar{v}), \\ S_{uu} &= \sum_j (u_j - \bar{u})^2, \quad S_{vv} = \sum_j (v_j - \bar{v})^2, \\ S_{uv} &= \sum_j (u_j - \bar{u})(v_j - \bar{v}). \end{aligned} \quad (\text{A3})$$

When (\bar{u}, \bar{v}) is chosen such that $\sum_j (u_j - \bar{u}) = \sum_j (v_j - \bar{v}) = 0$, $S_u = S_v = 0$, and thus the matrix inversion simplifies significantly.

We clip the linear estimate of $V(u, v)$ when the difference between the average visibility, $N^{-1} \sum_j V_j$, and \bar{V} exceeds the standard deviation of the V_j by more than a factor of 10. For Gaussian errors, the above procedure results in an unbiased estimator of \bar{V} and (V_u, V_v) .

The reconstruction of the offset and gradient in V is illustrated in Figure 17. Decreasing the number of data points and increasing the random error component increases the error in the reconstructed trend, unsurprisingly. Nevertheless, even for very few points the distribution of reconstructed trends covers the “truth” values faithfully (see Figure 18).




Figure 18. Distributions of reconstructed \bar{V} , V_u , and V_v for a specific realization of the (u, v) -positions generated upon varying a set of 10 complex V_j within a complex error of magnitude 0.1 Jy with fixed (u_j, v_j) . The underlying truth values are indicated by the vertical black lines.

Because we ultimately estimate the impact of the intrinsic uncertainties on the azimuthally averaged means and variances of the visibility amplitudes, we make no attempt during detrending to estimate the uncertainty on the $V(u, v)$ itself.

Appendix B Correlation-induced Bias

We employ a minor variation of the standard variance estimator to approximate the variance of the visibility amplitudes within each (u, v) -patch, which is then averaged to produce an estimate at each baseline length bin. However, where strong correlations exist between visibility amplitudes within a patch, they will result in significant biases. Gaining insight into the impact of these correlations is complicated by its heteroscedastic nature: strong correlations will exist within a patch on a single baseline but typically will not extend among different baselines.

Therefore, we construct a toy example in which the sequence of visibility amplitudes within a patch is composed of a sequence of N sets of replicas, each individually containing n_j perfectly correlated values (i.e., copies). That is, the set of




Figure 19. Debias factor associated with $M = 10$ total points apportioned randomly among $N = 2, 3, 5,$ and 10 sets of replicas.

values is

$$\{V\} = \{\{V_1, V_1, \dots\}, \dots, \{V_N, V_N, \dots\}\}. \quad (\text{B1})$$

The total number of values is

$$M = \sum_j^N n_j, \quad (\text{B2})$$

of which only N are independent. We further assume that the V_j are drawn from some distribution with variance σ^2 .

On average, the standard variance estimate from this sequence is































































































$$\langle \sigma_{\text{est}}^2 \rangle = \frac{M - \bar{n}^2 / \bar{n}^2}{M - 1} \sigma^2. \quad (\text{B3})$$

If $n_j = 1$ for all j , then $\bar{n}^2 = \bar{n}^2 = 1$ and the above reduces to the unbiased estimate. However, when n_j is not unity generally, a bias is induced in the estimated variance, becoming large when N is small.

The magnitude of the bias depends most sensitively on the number of replicas, i.e., N . Figure 19 shows the average debias factor for different values of N . When N is small, the value of the debias factor can easily reach values well above those measured in Section 4.5.

ORCID iDs

Avery E. Broderick <https://orcid.org/0000-0002-3351-760X>
 Roman Gold <https://orcid.org/0000-0003-2492-1966>
 Boris Georgiev <https://orcid.org/0000-0002-3586-6424>
 Dominic W. Pesce <https://orcid.org/0000-0002-5278-9221>
 Paul Tiede <https://orcid.org/0000-0003-3826-5648>
 Chunchong Ni <https://orcid.org/0000-0003-1361-5699>
 Kotaro Moriyama <https://orcid.org/0000-0003-1364-3761>
 Kazunori Akiyama <https://orcid.org/0000-0002-9475-4254>
 Antxon Alberdi <https://orcid.org/0000-0002-9371-1033>
 Juan Carlos Algaba <https://orcid.org/0000-0001-6993-1696>
 Richard Anantua <https://orcid.org/0000-0003-3457-7660>
 Keiichi Asada <https://orcid.org/0000-0001-6988-8763>
 Rebecca Azulay <https://orcid.org/0000-0002-2200-5393>
 Uwe Bach <https://orcid.org/0000-0002-7722-8412>

- Anne-Kathrin Baczko  <https://orcid.org/0000-0003-3090-3975>
- Mislav Baloković  <https://orcid.org/0000-0003-0476-6647>
- John Barrett  <https://orcid.org/0000-0002-9290-0764>
- Michi Bauböck  <https://orcid.org/0000-0002-5518-2812>
- Bradford A. Benson  <https://orcid.org/0000-0002-5108-6823>
- Lindy Blackburn  <https://orcid.org/0000-0002-9030-642X>
- Raymond Blundell  <https://orcid.org/0000-0002-5929-5857>
- Katherine L. Bouman  <https://orcid.org/0000-0003-0077-4367>
- Geoffrey C. Bower  <https://orcid.org/0000-0003-4056-9982>
- Hope Boyce  <https://orcid.org/0000-0002-6530-5783>
- Christiaan D. Brinkerink  <https://orcid.org/0000-0002-2322-0749>
- Roger Brissenden  <https://orcid.org/0000-0002-2556-0894>
- Silke Britzen  <https://orcid.org/0000-0001-9240-6734>
- Dominique Brogiere  <https://orcid.org/0000-0001-9151-6683>
- Thomas Bronzwaer  <https://orcid.org/0000-0003-1151-3971>
- Sandra Bustamante  <https://orcid.org/0000-0001-6169-1894>
- Do-Young Byun  <https://orcid.org/0000-0003-1157-4109>
- John E. Carlstrom  <https://orcid.org/0000-0002-2044-7665>
- Chiara Ceccobello  <https://orcid.org/0000-0002-4767-9925>
- Andrew Chael  <https://orcid.org/0000-0003-2966-6220>
- Chi-kwan Chan  <https://orcid.org/0000-0001-6337-6126>
- Koushik Chatterjee  <https://orcid.org/0000-0002-2825-3590>
- Shami Chatterjee  <https://orcid.org/0000-0002-2878-1502>
- Ming-Tang Chen  <https://orcid.org/0000-0001-6573-3318>
- Yongjun Chen (陈永军)  <https://orcid.org/0000-0001-5650-6770>
- Xiaopeng Cheng  <https://orcid.org/0000-0003-4407-9868>
- Ilje Cho  <https://orcid.org/0000-0001-6083-7521>
- Pierre Christian  <https://orcid.org/0000-0001-6820-9941>
- Nicholas S. Conroy  <https://orcid.org/0000-0003-2886-2377>
- John E. Conway  <https://orcid.org/0000-0003-2448-9181>
- James M. Cordes  <https://orcid.org/0000-0002-4049-1882>
- Thomas M. Crawford  <https://orcid.org/0000-0001-9000-5013>
- Geoffrey B. Crew  <https://orcid.org/0000-0002-2079-3189>
- Alejandro Cruz-Osorio  <https://orcid.org/0000-0002-3945-6342>
- Yuzhu Cui (崔玉竹)  <https://orcid.org/0000-0001-6311-4345>
- Jordy Davelaar  <https://orcid.org/0000-0002-2685-2434>
- Mariafelicia De Laurentis  <https://orcid.org/0000-0002-9945-682X>
- Roger Deane  <https://orcid.org/0000-0003-1027-5043>
- Jessica Dempsey  <https://orcid.org/0000-0003-1269-9667>
- Gregory Desvignes  <https://orcid.org/0000-0003-3922-4055>
- Jason Dexter  <https://orcid.org/0000-0003-3903-0373>
- Vedant Dhruv  <https://orcid.org/0000-0001-6765-877X>
- Sheperd S. Doeleman  <https://orcid.org/0000-0002-9031-0904>
- Sean Dougal  <https://orcid.org/0000-0002-3769-1314>
- Sergio A. Dzib  <https://orcid.org/0000-0001-6010-6200>
- Ralph P. Eatough  <https://orcid.org/0000-0001-6196-4135>
- Razieh Emami  <https://orcid.org/0000-0002-2791-5011>
- Heino Falcke  <https://orcid.org/0000-0002-2526-6724>
- Joseph Farah  <https://orcid.org/0000-0003-4914-5625>
- Vincent L. Fish  <https://orcid.org/0000-0002-7128-9345>
- Ed Fomalont  <https://orcid.org/0000-0002-9036-2747>
- H. Alyson Ford  <https://orcid.org/0000-0002-9797-0972>
- Raquel Fraga-Encinas  <https://orcid.org/0000-0002-5222-1361>
- Per Friberg  <https://orcid.org/0000-0002-8010-8454>
- Christian M. Fromm  <https://orcid.org/0000-0002-1827-1656>
- Antonio Fuentes  <https://orcid.org/0000-0002-8773-4933>
- Peter Galison  <https://orcid.org/0000-0002-6429-3872>
- Charles F. Gammie  <https://orcid.org/0000-0001-7451-8935>
- Roberto García  <https://orcid.org/0000-0002-6584-7443>
- Olivier Gentaz  <https://orcid.org/0000-0002-1115-4605>
- Ciriaco Goddi  <https://orcid.org/0000-0002-2542-7743>
- Arturo I. Gómez-Ruiz  <https://orcid.org/0000-0001-9395-1670>
- José L. Gómez  <https://orcid.org/0000-0003-4190-7613>
- Minfeng Gu (顾敏峰)  <https://orcid.org/0000-0002-4455-6946>
- Mark Gurwell  <https://orcid.org/0000-0003-0685-3621>
- Kazuhiro Hada  <https://orcid.org/0000-0001-6906-772X>
- Daryl Haggard  <https://orcid.org/0000-0001-6803-2138>
- Michael H. Hecht  <https://orcid.org/0000-0002-4114-4583>
- Ronald Hesper  <https://orcid.org/0000-0003-1918-6098>
- Dirk Heumann  <https://orcid.org/0000-0002-7671-0047>
- Luis C. Ho (何子山)  <https://orcid.org/0000-0001-6947-5846>
- Paul Ho  <https://orcid.org/0000-0002-3412-4306>
- Mareki Honma  <https://orcid.org/0000-0003-4058-9000>
- Chih-Wei L. Huang (黄磊)  <https://orcid.org/0000-0001-5641-3953>
- Lei Huang  <https://orcid.org/0000-0002-1923-227X>
- Shiro Ikeda  <https://orcid.org/0000-0002-2462-1448>
- C. M. Violette Impellizzeri  <https://orcid.org/0000-0002-3443-2472>
- Sara Issaoun  <https://orcid.org/0000-0002-5297-921X>
- David J. James  <https://orcid.org/0000-0001-5160-4486>
- Buell T. Jannuzi  <https://orcid.org/0000-0002-1578-6582>
- Michael Janssen  <https://orcid.org/0000-0001-8685-6544>
- Britton Jeter  <https://orcid.org/0000-0003-2847-1712>
- Wu Jiang (江悟)  <https://orcid.org/0000-0001-7369-3539>
- Alejandra Jiménez-Rosales  <https://orcid.org/0000-0002-2662-3754>
- Michael D. Johnson  <https://orcid.org/0000-0002-4120-3029>
- Svetlana Jorstad  <https://orcid.org/0000-0001-6158-1708>
- Abhishek V. Joshi  <https://orcid.org/0000-0002-2514-5965>
- Taehyun Jung  <https://orcid.org/0000-0001-7003-8643>
- Mansour Karami  <https://orcid.org/0000-0001-7387-9333>
- Ramesh Karuppusamy  <https://orcid.org/0000-0002-5307-2919>
- Tomohisa Kawashima  <https://orcid.org/0000-0001-8527-0496>
- Garrett K. Keating  <https://orcid.org/0000-0002-3490-146X>
- Mark Kettenis  <https://orcid.org/0000-0002-6156-5617>
- Dong-Jin Kim  <https://orcid.org/0000-0002-7038-2118>
- Jae-Young Kim  <https://orcid.org/0000-0001-8229-7183>
- Jongsoo Kim  <https://orcid.org/0000-0002-1229-0426>
- Junhan Kim  <https://orcid.org/0000-0002-4274-9373>
- Motoki Kino  <https://orcid.org/0000-0002-2709-7338>
- Jun Yi Koay  <https://orcid.org/0000-0002-7029-6658>
- Prashant Kocherlakota  <https://orcid.org/0000-0001-7386-7439>
- Patrick M. Koch  <https://orcid.org/0000-0003-2777-5861>
- Shoko Koyama  <https://orcid.org/0000-0002-3723-3372>

- Carsten Kramer  <https://orcid.org/0000-0002-4908-4925>
Michael Kramer  <https://orcid.org/0000-0002-4175-2271>
Thomas P. Krichbaum  <https://orcid.org/0000-0002-4892-9586>
Cheng-Yu Kuo  <https://orcid.org/0000-0001-6211-5581>
Noemi La Bella  <https://orcid.org/0000-0002-8116-9427>
Tod R. Lauer  <https://orcid.org/0000-0003-3234-7247>
Daeyoung Lee  <https://orcid.org/0000-0002-3350-5588>
Sang-Sung Lee  <https://orcid.org/0000-0002-6269-594X>
Po Kin Leung  <https://orcid.org/0000-0002-8802-8256>
Aviad Levis  <https://orcid.org/0000-0001-7307-632X>
Zhiyuan Li (李志远)  <https://orcid.org/0000-0003-0355-6437>
Rocco Lico  <https://orcid.org/0000-0001-7361-2460>
Greg Lindahl  <https://orcid.org/0000-0002-6100-4772>
Michael Lindqvist  <https://orcid.org/0000-0002-3669-0715>
Mikhail Lisakov  <https://orcid.org/0000-0001-6088-3819>
Jun Liu (刘俊)  <https://orcid.org/0000-0002-7615-7499>
Kuo Liu  <https://orcid.org/0000-0002-2953-7376>
Elisabetta Liuzzo  <https://orcid.org/0000-0003-0995-5201>
Wen-Ping Lo  <https://orcid.org/0000-0003-1869-2503>
Andrei P. Lobanov  <https://orcid.org/0000-0003-1622-1484>
Laurent Loinard  <https://orcid.org/0000-0002-5635-3345>
Colin J. Lonsdale  <https://orcid.org/0000-0003-4062-4654>
Ru-Sen Lu (路如森)  <https://orcid.org/0000-0002-7692-7967>
Jirong Mao (毛基荣)  <https://orcid.org/0000-0002-7077-7195>
Nicola Marchili  <https://orcid.org/0000-0002-5523-7588>
Sera Markoff  <https://orcid.org/0000-0001-9564-0876>
Daniel P. Marrone  <https://orcid.org/0000-0002-2367-1080>
Alan P. Marscher  <https://orcid.org/0000-0001-7396-3332>
Iván Martí-Vidal  <https://orcid.org/0000-0003-3708-9611>
Satoki Matsushita  <https://orcid.org/0000-0002-2127-7880>
Lynn D. Matthews  <https://orcid.org/0000-0002-3728-8082>
Karl M. Menten  <https://orcid.org/0000-0001-6459-0669>
Daniel Michalik  <https://orcid.org/0000-0002-7618-6556>
Izumi Mizuno  <https://orcid.org/0000-0002-7210-6264>
Yosuke Mizuno  <https://orcid.org/0000-0002-8131-6730>
James M. Moran  <https://orcid.org/0000-0002-3882-4414>
Monika Moscibrodzka  <https://orcid.org/0000-0002-4661-6332>
Cornelia Müller  <https://orcid.org/0000-0002-2739-2994>
Alejandro Mus  <https://orcid.org/0000-0003-0329-6874>
Gibwa Musoke  <https://orcid.org/0000-0003-1984-189X>
Ioannis Myserlis  <https://orcid.org/0000-0003-3025-9497>
Andrew Nadolski  <https://orcid.org/0000-0001-9479-9957>
Hiroshi Nagai  <https://orcid.org/0000-0003-0292-3645>
Neil M. Nagar  <https://orcid.org/0000-0001-6920-662X>
Masanori Nakamura  <https://orcid.org/0000-0001-6081-2420>
Ramesh Narayan  <https://orcid.org/0000-0002-1919-2730>
Gopal Narayanan  <https://orcid.org/0000-0002-4723-6569>
Iniyan Natarajan  <https://orcid.org/0000-0001-8242-4373>
Joey Neilsen  <https://orcid.org/0000-0002-8247-786X>
Roberto Neri  <https://orcid.org/0000-0002-7176-4046>
Aristeidis Noutsos  <https://orcid.org/0000-0002-4151-3860>
Michael A. Nowak  <https://orcid.org/0000-0001-6923-1315>
Junghwan Oh  <https://orcid.org/0000-0002-4991-9638>
Hiroki Okino  <https://orcid.org/0000-0003-3779-2016>
Héctor Olivares  <https://orcid.org/0000-0001-6833-7580>
Gisela N. Ortiz-León  <https://orcid.org/0000-0002-2863-676X>
Tomoaki Oyama  <https://orcid.org/0000-0003-4046-2923>
Daniel C. M. Palumbo  <https://orcid.org/0000-0002-7179-3816>
Georgios Filippas Paraschos  <https://orcid.org/0000-0001-6757-3098>
Jongho Park  <https://orcid.org/0000-0001-6558-9053>
Harriet Parsons  <https://orcid.org/0000-0002-6327-3423>
Nimesh Patel  <https://orcid.org/0000-0002-6021-9421>
Ue-Li Pen  <https://orcid.org/0000-0003-2155-9578>
Richard Plambeck  <https://orcid.org/0000-0001-6765-9609>
Oliver Porth  <https://orcid.org/0000-0002-4584-2557>
Felix M. Pözl  <https://orcid.org/0000-0002-6579-8311>
Ben Prather  <https://orcid.org/0000-0002-0393-7734>
Jorge A. Preciado-López  <https://orcid.org/0000-0002-4146-0113>
Hung-Yi Pu  <https://orcid.org/0000-0001-9270-8812>
Venkatesh Ramakrishnan  <https://orcid.org/0000-0002-9248-086X>
Ramprasad Rao  <https://orcid.org/0000-0002-1407-7944>
Mark G. Rawlings  <https://orcid.org/0000-0002-6529-202X>
Alexander W. Raymond  <https://orcid.org/0000-0002-5779-4767>
Luciano Rezzolla  <https://orcid.org/0000-0002-1330-7103>
Angelo Ricarte  <https://orcid.org/0000-0001-5287-0452>
Bart Ripperda  <https://orcid.org/0000-0002-7301-3908>
Freek Roelofs  <https://orcid.org/0000-0001-5461-3687>
Alan Rogers  <https://orcid.org/0000-0003-1941-7458>
Eduardo Ros  <https://orcid.org/0000-0001-9503-4892>
Cristina Romero-Cañizales  <https://orcid.org/0000-0001-6301-9073>
Arash Roshanineshat  <https://orcid.org/0000-0002-8280-9238>
Alan L. Roy  <https://orcid.org/0000-0002-1931-0135>
Ignacio Ruiz  <https://orcid.org/0000-0002-0965-5463>
Chet Ruszczyk  <https://orcid.org/0000-0001-7278-9707>
Kazi L. J. Rygl  <https://orcid.org/0000-0003-4146-9043>
Salvador Sánchez  <https://orcid.org/0000-0002-8042-5951>
David Sánchez-Argüelles  <https://orcid.org/0000-0002-7344-9920>
Miguel Sánchez-Portal  <https://orcid.org/0000-0003-0981-9664>
Mahito Sasada  <https://orcid.org/0000-0001-5946-9960>
Kaushik Satapathy  <https://orcid.org/0000-0003-0433-3585>
Tuomas Savolainen  <https://orcid.org/0000-0001-6214-1085>
Jonathan Schonfeld  <https://orcid.org/0000-0002-8909-2401>
Karl-Friedrich Schuster  <https://orcid.org/0000-0003-2890-9454>
Lijing Shao  <https://orcid.org/0000-0002-1334-8853>
Zhiqiang Shen (沈志强)  <https://orcid.org/0000-0003-3540-8746>
Des Small  <https://orcid.org/0000-0003-3723-5404>
Bong Won Sohn  <https://orcid.org/0000-0002-4148-8378>
Jason SooHoo  <https://orcid.org/0000-0003-1938-0720>
Kamal Souccar  <https://orcid.org/0000-0001-7915-5272>
He Sun (孙赫)  <https://orcid.org/0000-0003-1526-6787>
Fumie Tazaki  <https://orcid.org/0000-0003-0236-0600>
Alexandra J. Tetarenko  <https://orcid.org/0000-0003-3906-4354>
Remo P. J. Tilanus  <https://orcid.org/0000-0002-6514-553X>
Michael Titus  <https://orcid.org/0000-0001-9001-3275>

Pablo Torne  <https://orcid.org/0000-0001-8700-6058>
 Efthalia Traianou  <https://orcid.org/0000-0002-1209-6500>
 Sascha Trippe  <https://orcid.org/0000-0003-0465-1559>
 Matthew Turk  <https://orcid.org/0000-0002-5294-0198>
 Ilse van Bemmell  <https://orcid.org/0000-0001-5473-2950>
 Huib Jan van Langevelde  <https://orcid.org/0000-0002-0230-5946>
 Daniel R. van Rossum  <https://orcid.org/0000-0001-7772-6131>
 Jesse Vos  <https://orcid.org/0000-0003-3349-7394>
 Jan Wagner  <https://orcid.org/0000-0003-1105-6109>
 Derek Ward-Thompson  <https://orcid.org/0000-0003-1140-2761>
 John Wardle  <https://orcid.org/0000-0002-8960-2942>
 Jonathan Weintraub  <https://orcid.org/0000-0002-4603-5204>
 Norbert Wex  <https://orcid.org/0000-0003-4058-2837>
 Robert Wharton  <https://orcid.org/0000-0002-7416-5209>
 Maciek Wielgus  <https://orcid.org/0000-0002-8635-4242>
 Kaj Wiik  <https://orcid.org/0000-0002-0862-3398>
 Gunther Witzel  <https://orcid.org/0000-0003-2618-797X>
 Michael F. Wondrak  <https://orcid.org/0000-0002-6894-1072>
 George N. Wong  <https://orcid.org/0000-0001-6952-2147>
 Qingwen Wu (吴庆文)  <https://orcid.org/0000-0003-4773-4987>
 Paul Yamaguchi  <https://orcid.org/0000-0002-6017-8199>
 Doosoo Yoon  <https://orcid.org/0000-0001-8694-8166>
 André Young  <https://orcid.org/0000-0003-0000-2682>
 Ken Young  <https://orcid.org/0000-0002-3666-4920>
 Ziri Younsi  <https://orcid.org/0000-0001-9283-1191>
 Feng Yuan (袁峰)  <https://orcid.org/0000-0003-3564-6437>
 Ye-Fei Yuan (袁业飞)  <https://orcid.org/0000-0002-7330-4756>
 J. Anton Zensus  <https://orcid.org/0000-0001-7470-3321>
 Guang-Yao Zhao  <https://orcid.org/0000-0002-4417-1659>
 Shuo Zhang  <https://orcid.org/0000-0002-2967-790X>
 Shan-Shan Zhao (赵彬彬)  <https://orcid.org/0000-0002-9774-3606>

References

- Arras, P., Frank, P., Haim, P., et al. 2022, *NatAs*, 6, 259
 Arras, P., Frank, P., Leike, R., Westermann, R., & Enßlin, T. A. 2019, *A&A*, 627, A134
 Bouman, K. L., Johnson, M. D., Dalca, A. V., et al. 2018, *IEEE Trans Comput Imaging*, 4, 512
 Boyce, H., Haggard, D., Witzel, G., et al. 2019, *ApJ*, 871, 161
 Broderick, A. E., Gold, R., Karami, M., et al. 2020a, *ApJ*, 897, 139
 Broderick, A. E., Pesce, D. W., Tiede, P., Pu, H.-Y., & Gold, R. 2020b, *ApJ*, 898, 9
 Dexter, J., Kelly, B., Bower, G. C., et al. 2014, *MNRAS*, 442, 2797
 Do, T., Hees, A., Ghez, A., et al. 2019, *Sci*, 365, 664
 Event Horizon Telescope Collaboration, Akiyama, K., Alberdi, A., et al. 2019a, *ApJL*, 875, L1, (Paper I)
 Event Horizon Telescope Collaboration, Akiyama, K., Alberdi, A., et al. 2019b, *ApJL*, 875, L2, (Paper II)
 Event Horizon Telescope Collaboration, Akiyama, K., Alberdi, A., et al. 2019c, *ApJL*, 875, L3, (Paper III)
 Event Horizon Telescope Collaboration, Akiyama, K., Alberdi, A., et al. 2019d, *ApJL*, 875, L4, (Paper IV)
 Event Horizon Telescope Collaboration, Akiyama, K., Alberdi, A., et al. 2019e, *ApJL*, 875, L5, (Paper V)
 Event Horizon Telescope Collaboration, Akiyama, K., Alberdi, A., et al. 2019f, *ApJL*, 875, L6, (Paper VI)
 Event Horizon Telescope Collaboration, Akiyama, K., Alberdi, A., et al. 2022a, *ApJL*, 930, L12, (Paper I)
 Event Horizon Telescope Collaboration, Akiyama, K., Alberdi, A., et al. 2022b, *ApJL*, 930, L13, (Paper II)
 Event Horizon Telescope Collaboration, Akiyama, K., Alberdi, A., et al. 2021c, *ApJL*, 930, L14, Paper (III)
 Event Horizon Telescope Collaboration, Akiyama, K., Alberdi, A., et al. 2022d, *ApJL*, 930, L15, (Paper IV)
 Event Horizon Telescope Collaboration, Akiyama, K., Alberdi, A., et al. 2022e, *ApJL*, 930, L16, (Paper V)
 Event Horizon Telescope Collaboration, Akiyama, K., Alberdi, A., et al. 2022f, *ApJL*, 930, L17, (Paper VI)
 Fish, V. L., Doeleman, S. S., Beaudoin, C., et al. 2011, *ApJL*, 727, L36
 Fomalont, E. B., Geldzahler, B. J., & Bradshaw, C. F. 2001, *ApJ*, 558, 283
 Foreman-Mackey, D., Hogg, D. W., Lang, D., & Goodman, J. 2013, *PASP*, 125, 306
 Georgiev, B., Pesce, D. W., Broderick, A. E., et al. 2022, *ApJL*, 930, L20
 Gold, R., Broderick, A. E., Younsi, Z., et al. 2020, *ApJ*, 897, 148
 Gravity Collaboration, Abuter, R., Amorim, A., et al. 2018, *A&A*, 618, L10
 Gravity Collaboration, Abuter, R., Amorim, A., et al. 2019, *A&A*, 625, L10
 Gravity Collaboration, Abuter, R., Amorim, A., et al. 2020, *A&A*, 636, L5
 Issaoun, S., Johnson, M. D., Blackburn, L., et al. 2021, *ApJ*, 915, 99
 Janssen, M., Falcke, H., Kadler, M., et al. 2021, *NatAs*, 5, 1017
 Johnson, M. D., Bouman, K. L., Blackburn, L., et al. 2017, *ApJ*, 850, 172
 Johnson, M. D., Lupsasca, A., Strominger, A., et al. 2020, *SciA*, 6, eaaz1310
 Johnson, M. D., Narayan, R., Psaltis, D., et al. 2018, *ApJ*, 865, 104
 Kim, J.-Y., Krichbaum, T. P., Broderick, A. E., et al. 2020, *A&A*, 640, A69
 Lee, D., & Gammie, C. F. 2021, *ApJ*, 906, 39
 Lister, M. L., Aller, M. F., Aller, H. D., et al. 2018, *ApJS*, 234, 12
 Lu, R.-S., Roelofs, F., Fish, V. L., et al. 2016, *ApJ*, 817, 173
 Matthews, L. D., Greenhill, L. J., Goddi, C., et al. 2010, *ApJ*, 708, 80
 Miller-Jones, J. C. A., Tetarenko, A. J., Sivakoff, G. R., et al. 2019, *Natur*, 569, 374
 Pesce, D. W. 2021, *AJ*, 161, 178
 Roelofs, F., Fromm, C. M., Mizuno, Y., et al. 2021, *A&A*, 650, A56
 Roelofs, F., Johnson, M. D., Shiokawa, H., Doeleman, S. S., & Falcke, H. 2017, *ApJ*, 847, 55
 Satapathy, K., Psaltis, D., Özel, F., et al. 2022, *ApJ*, 925, 13
 Thompson, A. R., Moran, J. M., & Swenson, G. W., Jr. 2017, *Interferometry and Synthesis in Radio Astronomy* (Cham: Springer)
 Walker, R. C., Hardee, P. E., Davies, F. B., Ly, C., & Junor, W. 2018, *ApJ*, 855, 128
 Wielgus, M., Marchili, N., Martí-Vidal, I., et al. 2022, *ApJL*, 930, L19
 Witzel, G., Martínez, G., Hora, J., et al. 2018, *ApJ*, 863, 15
 Witzel, G., Martínez, G., Willner, S. P., et al. 2021, *ApJ*, 917, 73